# Colorado Department Of Transportation Low Bid Summary

Page 1 of 1

08/06/2020

Printed On:

Letting Date: August 06, 2020

Call Order	Contract ID	Project(s)	# of Bids	Low Bidder	Estimated Cost	Corrected Bid	Percent of Estimate	Overrun (+) Underrun (-)
005	C21453	STR184B-006	1	AMERICAN WEST CONSTRUCTION, LLC	\$499,884.00	\$497,913.75	99.61%	-\$1,970.25
Letti	ng Totals		1		\$499,884.00	\$497,913.75	99.61%	-\$1,970.25

#### **Vendor Ranking**

Printed On: Page 1 of 1

08/06/2020

Contract ID: C21453

**Contract Description:** 

SH 184 MM 11.73 AND MM 12.29

This project consists of the rehabilitation of 5 culverts along SH 184 in SW Colorado. Locations are Mile Markers 11.73, 12.29, 12.57, 12.83 and 14.01. The rehab methods as shown in the plans call for a spray applied lining with cement grout to be used to fill voids in the existing cmp culverts. Also included in the project but not limited to is placement of riprap, removal and replacement of guardrail and end sections, extending existing guardrail runs, erosion control and traffic control.

This project has an optional on-site job showing on July 28th between the hours of 2:30 to 3:30 pm.

Notification of planned attendance is required by July 24th to the Resident Engineer.

Rank	Vendor ID	Vendor Name	Total Bid	Percent Of Low Bid	Percent Of Estimate
1	1282A	AMERICAN WEST CONSTRUCTION, LLC	\$497,913.75	100.00%	99.61%
0	-EST-	Engineer's Estimate	\$499,884.00	100.40%	100.00%

#### **Tabulation of Bids**

#### Page 1 of 3

08/06/2020

Printed On:

			(0) -EST- Engineer's Estimate		` ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' ' '			
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
202-01300	Removal of End Anchorage	2.000 EACH	400.00000	800.00	350.00000	700.00		
202-04002	Clean Culvert	5.000 EACH	5,000.00000	25,000.00	4,900.00000	24,500.00		
203-00060	Embankment Material (Complete In Place)	27.000 CY	180.00000	4,860.00	170.00000	4,590.00		
203-01594	Combination Loader	25.000 HOUR	150.00000	3,750.00	110.00000	2,750.00		
203-01597	Potholing	40.000 HOUR	250.00000	10,000.00	260.00000	10,400.00		
203-02330	Laborer	25.000 HOUR	50.00000	1,250.00	55.00000	1,375.00		
206-00000	Structure Excavation	71.000 CY	50.00000	3,550.00	75.00000	5,325.00		
206-00100	Structure Backfill (Class 1)	9.000 CY	200.00000	1,800.00	230.00000	2,070.00		
207-00700	Topsoil (Onsite)	121.000 CY	25.00000	3,025.00	46.50000	5,626.50		
208-00008	Erosion Log Type 2 (12 Inch)	625.000 LF	7.00000	4,375.00	7.75000	4,843.75		
208-00046	Pre-fabricated Concrete Washout Structure (Type 1)	1.000 EACH	600.00000	600.00	3,000.00000	3,000.00		
208-00103	Removal and Disposal of Sediment (Labor)	100.000 HOUR	60.00000	6,000.00	55.00000	5,500.00		
208-00105	Removal and Disposal of Sediment (Equipment)	40.000 HOUR	180.00000	7,200.00	110.00000	4,400.00		
208-00106	Sweeping (Sediment Removal)	30.000 HOUR	115.00000	3,450.00	110.00000	3,300.00		
211-02277	Cement Grout (Voids)	11.000 CY	1,725.00000	18,975.00	750.00000	8,250.00		

#### **Tabulation of Bids**

#### Page 2 of 3

08/06/2020

Printed On:

			(0) -EST- Engineer's Estimate		(1) 1282A AMERICAN WEST CONSTRUCTION, LLC			
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
212-00006	Seeding (Native)	0.340 ACRE	5,000.00000	1,700.00	2,200.00000	748.00		
212-00028	Seeding (Wetlands)	0.010 ACRE	6,400.00000	64.00	25,000.00000	250.00		
212-00032	Soil Conditioning	0.340 ACRE	6,000.00000	2,040.00	6,000.00000	2,040.00		
213-00004	Mulching (Weed Free Straw)	0.350 ACRE	5,000.00000	1,750.00	2,100.00000	735.00		
213-00061	Mulch Tackifier	64.000 LB	20.00000	1,280.00	8.00000	512.00		
240-00000	Wildlife Biologist	30.000 HOUR	150.00000	4,500.00	125.00000	3,750.00		
420-00133	Geotextile (Separator) (Class 2)	70.000 SY	40.00000	2,800.00	21.00000	1,470.00		
506-00218	Riprap (18 Inch)	60.000 CY	225.00000	13,500.00	265.00000	15,900.00		
601-01000	Concrete Class B	2.000 CY	2,250.00000	4,500.00	6,100.00000	12,200.00		
603-00043	Culvert Lining (42 Inch)(Spray Applied)	865.500 LF	250.00000	216,375.00	295.00000	255,322.50		
606-00301	Guardrail Type 3 (6-3 Post Spacing)	200.000 LF	45.00000	9,000.00	32.00000	6,400.00		
606-01385	Transition Type 3J	1.000 EACH	3,000.00000	3,000.00	2,700.00000	2,700.00		
606-01390	End Anchorage Type 3K	1.000 EACH	3,300.00000	3,300.00	2,800.00000	2,800.00		
606-02003	End Anchorage (Nonflared)	1.000 EACH	4,000.00000	4,000.00	3,800.00000	3,800.00		
607-11525	Fence (Plastic)	300.000 LF	5.00000	1,500.00	3.00000	900.00		
612-00003	Delineator (Type III)	10.000 EACH	80.00000	800.00	110.00000	1,100.00		

#### **Tabulation of Bids**

#### Page 3 of 3

08/06/2020

Printed On:

				- timate	(1) 1282 AMERICAN CONSTRUCTI	WEST		
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
620-00020	Sanitary Facility	1.000 EACH	3,000.00000	3,000.00	440.00000	440.00		
625-00000	Construction Surveying	1.000 LS	10,000.00000	10,000.00	3,000.00000	3,000.00		
626-00000	Mobilization	1.000 LS	49,000.00000	49,000.00	49,000.00000	49,000.00		
626-01114	Public Information Management (Tier IV)	68.000 DAY	80.00000	5,440.00	50.00000	3,400.00		
630-00000	Flagging	910.000 HOUR	27.00000	24,570.00	21.50000	19,565.00		
630-00007	Traffic Control Inspection	17.000 DAY	200.00000	3,400.00	80.00000	1,360.00		
630-00012	Traffic Control Management	35.000 DAY	800.0000	28,000.00	510.00000	17,850.00		
630-80341	Construction Traffic Sign (Panel Size A)	22.000 EACH	35.00000	770.00	40.00000	880.00		
630-80342	Construction Traffic Sign (Panel Size B)	8.000 EACH	50.00000	400.00	40.00000	320.00		
630-80355	Portable Message Sign Panel	2.000 EACH	5,000.00000	10,000.00	2,300.00000	4,600.00		
630-80360	Drum Channelizing Device	12.000 EACH	30.00000	360.00	11.75000	141.00		
630-80380	Traffic Cone	40.000 EACH	5.00000	200.00	2.50000	100.00		
Section To	tals:		\$49	9,884.00	\$49	7,913.75		
Contract (	Grand Totals		\$49	99,884.00	\$49	97,913.75		

#### Low Bid Item Analysis

Page 1 of 4

08/06/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0005	202-01300 Removal of End	2.000 Anchorage	400.00000	350.00000 EACH	800.00	700.00	87.50%	-100.00
0010	202-04002 Clean Culvert	5.000	5,000.00000	4,900.00000 EACH	25,000.00	24,500.00	98.00%	-500.00
0015	203-00060 Embankment Ma	27.000 Iterial (Complete In	180.00000 Place)	170.00000 CY	4,860.00	4,590.00	94.44%	-270.00
0020	203-01594 Combination Loa	25.000 ider	150.00000	110.00000 HOUR	3,750.00	2,750.00	73.33%	-1,000.00
0025	203-01597 Potholing	40.000	250.00000	260.00000 HOUR	10,000.00	10,400.00	104.00%	400.00
0030	203-02330 Laborer	25.000	50.00000	55.00000 HOUR	1,250.00	1,375.00	110.00%	125.00
0035	206-00000 Structure Excava	71.000 ation	50.00000	75.00000 CY	3,550.00	5,325.00	150.00%	1,775.00
0040	206-00100 Structure Backfill	9.000 (Class 1)	200.00000	230.00000 CY	1,800.00	2,070.00	115.00%	270.00
0045	207-00700 Topsoil (Onsite)	121.000	25.00000	46.50000 CY	3,025.00	5,626.50	186.00%	2,601.50
0050	208-00008 Erosion Log Type	625.000 e 2 (12 Inch)	7.00000	7.75000 LF	4,375.00	4,843.75	110.71%	468.75
0055	208-00046 Pre-fabricated C (Type 1)	1.000 oncrete Washout S	600.00000 tructure	3,000.00000 EACH	600.00	3,000.00	500.00%	2,400.00
0060	208-00103 Removal and Dis	100.000 sposal of Sediment	60.00000 (Labor)	55.00000 HOUR	6,000.00	5,500.00	91.67%	-500.00

#### Low Bid Item Analysis

Page 2 of 4

08/06/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0065	208-00105 Removal and Disp	40.000 posal of Sediment	180.00000 (Equipment)	110.00000 HOUR	7,200.00	4,400.00	61.11%	-2,800.00
0070	208-00106 Sweeping (Sedim	30.000 ent Removal)	115.00000	110.00000 HOUR	3,450.00	3,300.00	95.65%	-150.00
0075	211-02277 Cement Grout (Vo	11.000 pids)	1,725.00000	750.00000 CY	18,975.00	8,250.00	43.48%	-10,725.00
0800	212-00006 Seeding (Native)	0.340	5,000.00000	2,200.00000 ACRE	1,700.00	748.00	44.00%	-952.00
0085	212-00028 Seeding (Wetland	0.010 s)	6,400.00000	25,000.00000 ACRE	64.00	250.00	390.63%	186.00
0090	212-00032 Soil Conditioning	0.340	6,000.00000	6,000.00000 ACRE	2,040.00	2,040.00	100.00%	0.00
0095	213-00004 Mulching (Weed F	0.350 Free Straw)	5,000.00000	2,100.00000 ACRE	1,750.00	735.00	42.00%	-1,015.00
0100	213-00061 Mulch Tackifier	64.000	20.00000	8.00000 LB	1,280.00	512.00	40.00%	-768.00
0105	240-00000 Wildlife Biologist	30.000	150.00000	125.00000 HOUR	4,500.00	3,750.00	83.33%	-750.00
0110	420-00133 Geotextile (Separ	70.000 ator) (Class 2)	40.00000	21.00000 SY	2,800.00	1,470.00	52.50%	-1,330.00
0115	506-00218 Riprap (18 Inch)	60.000	225.00000	265.00000 CY	13,500.00	15,900.00	117.78%	2,400.00
0120	601-01000 Concrete Class B	2.000	2,250.00000	6,100.00000 CY	4,500.00	12,200.00	271.11%	7,700.00

#### Low Bid Item Analysis

Page 3 of 4

08/06/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0125	603-00043 Culvert Lining (4	865.500 2 Inch)(Spray Appli	250.00000 ed)	295.00000 LF	216,375.00	255,322.50	118.00%	38,947.50
0130	606-00301 Guardrail Type 3	200.000 (6-3 Post Spacing)	45.00000 )	32.00000 LF	9,000.00	6,400.00	71.11%	-2,600.00
0135	606-01385 Transition Type 3	1.000 3J	3,000.00000	2,700.00000 EACH	3,000.00	2,700.00	90.00%	-300.00
0140	606-01390 End Anchorage	1.000 Гуре 3К	3,300.00000	2,800.00000 EACH	3,300.00	2,800.00	84.85%	-500.00
0145	606-02003 End Anchorage (	1.000 (Nonflared)	4,000.00000	3,800.00000 EACH	4,000.00	3,800.00	95.00%	-200.00
0150	607-11525 Fence (Plastic)	300.000	5.00000	3.00000 LF	1,500.00	900.00	60.00%	-600.00
0155	612-00003 Delineator (Type	10.000 III)	80.00000	110.00000 EACH	800.00	1,100.00	137.50%	300.00
0160	620-00020 Sanitary Facility	1.000	3,000.00000	440.00000 EACH	3,000.00	440.00	14.67%	-2,560.00
0165	625-00000 Construction Sur	1.000 veying	10,000.00000	3,000.00000 L S	10,000.00	3,000.00	30.00%	-7,000.00
0170	626-00000 Mobilization	1.000	49,000.00000	49,000.00000 L S	49,000.00	49,000.00	100.00%	0.00
0175	626-01114 Public Informatio	68.000 n Management (Tie	80.00000 er IV)	50.00000 DAY	5,440.00	3,400.00	62.50%	-2,040.00
0180	630-00000 Flagging	910.000	27.00000	21.50000 HOUR	24,570.00	19,565.00	79.63%	-5,005.00

#### Low Bid Item Analysis

Page 4 of 4

08/06/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0185	630-00007 Traffic Control In	17.000 spection	200.00000	80.00000 DAY	3,400.00	1,360.00	40.00%	-2,040.00
0190	630-00012 Traffic Control M	35.000 anagement	800.00000	510.00000 DAY	28,000.00	17,850.00	63.75%	-10,150.00
0195	630-80341 Construction Tra	22.000 iffic Sign (Panel Size	35.00000 e A)	40.00000 EACH	770.00	880.00	114.29%	110.00
0200	630-80342 Construction Tra	8.000 iffic Sign (Panel Size	50.00000 e B)	40.00000 EACH	400.00	320.00	80.00%	-80.00
0205	630-80355 Portable Messag	2.000 ge Sign Panel	5,000.00000	2,300.00000 EACH	10,000.00	4,600.00	46.00%	-5,400.00
0210	630-80360 Drum Channeliz	12.000 ing Device	30.00000	11.75000 EACH	360.00	141.00	39.17%	-219.00
0215	630-80380 Traffic Cone	40.000	5.00000	2.50000 EACH	200.00	100.00	50.00%	-100.00
Section 0	001 Subtotal				\$499,884.00	\$497,913.75	99.61%	-\$1,970.25
Contrac	ct Total for Cald	ulated Low Bidd	ers Bid Items		\$499,884.00	\$497,913.75	99.61%	-\$1,970.25