Colorado Department Of Transportation Low Bid Summary

Page 1 of 1

05/20/2021

Printed On:

Letting Date: May 13, 2021

Call Order	Order Contract ID Project(s) Bids		Low Bidder	Estimated Cost	Corrected Bid	Percent of Estimate	Overrun (+) Underrun (-)	
003	C19263	BR1602-139	6	KIEWIT INFRASTRUCTURE CO.	\$5,442,678.00	\$5,353,935.50	98.37%	-\$88,742.50
Letti	ng Totals		6		\$5,442,678.00	\$5,353,935.50	98.37%	-\$88,742.50

Colorado Department Of Transportation

Vendor Ranking

05/20/2021Page 1 of 1

Printed On:

Contract ID: C19263

Contract Description:

This project is located on US 160 in Pagosa Springs within Archuleta county. The work involves replacing twin 84" Culverts with a triple cell 14'x10'x92' Pre-Cast Concrete Box Culverts, inlet drop structures, establishing new downstream channel, Guardrail rail, Bridge rail, erosion control, traffic control, sidewalks, and fencing.

Rank	Vendor ID	Vendor Name	Total Bid	Percent Of Low Bid	Percent Of Estimate
1	695A	KIEWIT INFRASTRUCTURE CO.	\$5,353,935.50	100.00%	98.37%
0	-EST-	Engineer's Estimate	\$5,442,678.00	101.66%	100.00%
2	672A	OLDCASTLE SW GROUP, INC.	\$5,497,330.56	102.68%	101.00%
3	1415A	RALPH L. WADSWORTH CONSTRUCTION COMPANY, LLC.	\$5,973,733.91	111.58%	109.76%
4	1567A	Lobato Construction, LLC	\$6,183,272.15	115.49%	113.61%
5	045A	HANK WILLIAMS, INC. dba WILLIAMS CONSTRUCTION CONTRACTORS	\$6,379,683.27	119.16%	117.22%
6	101A	RMS UTILITIES, INC.	\$8,239,887.84	153.90%	151.39%

Page 1 of 33

05/20/2021

Printed On:

				(0) -EST Engineer's Es		(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SW GROUP, INC.		
Item Code	Description	Quai	ntity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	
SECTION:	0001 Roadway						LCC:			
201-00000	Clearing and Grubbing	1.000	LS	40,000.00000	40,000.00	20,000.00000	20,000.00	3,022.97000	3,022.97	
202-00010	Removal of Tree	5.000	EACH	250.00000	1,250.00	1,000.00000	5,000.00	1,162.11000	5,810.55	
202-00019	Removal of Inlet	2.000	EACH	2,000.00000	4,000.00	2,000.00000	4,000.00	1,734.25000	3,468.50	
202-00021	Removal of Manhole	1.000	EACH	2,500.00000	2,500.00	2,500.00000	2,500.00	3,637.45000	3,637.45	
202-00035	Removal of Pipe	792.000	LF	40.00000	31,680.00	45.00000	35,640.00	39.78000	31,505.76	
202-00155	Removal of Wall	18.000	LF	150.00000	2,700.00	110.00000	1,980.00	94.47000	1,700.46	
202-00200	Removal of Sidewalk	336.000	SY	40.00000	13,440.00	25.00000	8,400.00	20.09000	6,750.24	
202-00202	Removal of Gutter	42.000	LF	30.00000	1,260.00	60.00000	2,520.00	34.56000	1,451.52	
202-00203	Removal of Curb and Gutter	605.000	LF	20.00000	12,100.00	20.00000	12,100.00	10.77000	6,515.85	
202-00220	Removal of Asphalt Mat	4,477.000	SY	15.00000	67,155.00	6.00000	26,862.00	8.25000	36,935.25	
202-00250	Removal of Pavement Marking	1,418.000	SF	5.00000	7,090.00	3.00000	4,254.00	3.25000	4,608.50	
202-00810	Removal of Ground Sign	6.000	EACH	150.00000	900.00	250.00000	1,500.00	239.22000	1,435.32	
202-01000	Removal of Fence	188.000	LF	4.00000	752.00	11.00000	2,068.00	5.80000	1,090.40	
203-00000	Unclassified Excavation	11,609.000	CY	25.00000	290,225.00	12.00000	139,308.00	18.03000	209,310.27	
203-00400	Rock Excavation	4,775.000	CY	70.00000	334,250.00	30.00000	143,250.00	30.42000	145,255.50	
203-01500	Blading	80.000	HOUR	150.00000	12,000.00	160.00000	12,800.00	118.70000	9,496.00	

Page 2 of 33

05/20/2021

Printed On:

				(0) -EST Engineer's Es		(1) 695 KIEWI INFRASTRUCT	Т	(2) 672 OLDCASTL GROUP,	E SW
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
203-01510	Backhoe	40.000 H	IOUR	150.00000	6,000.00	140.00000	5,600.00	136.64000	5,465.60
203-01597	Potholing	80.000 ⊦	IOUR	250.00000	20,000.00	400.00000	32,000.00	424.61000	33,968.80
203-01622	Sweeping (With Pickup Broom)	20.000 H	IOUR	200.00000	4,000.00	250.00000	5,000.00	196.61000	3,932.20
203-02330	Laborer	40.000 H	IOUR	60.00000	2,400.00	50.00000	2,000.00	48.31000	1,932.40
206-00000	Structure Excavation	3,586.000	CY	30.00000	107,580.00	20.00000	71,720.00	29.59000	106,109.74
206-00065	Structure Backfill (Flow-Fill)	366.000	CY	230.00000	84,180.00	300.00000	109,800.00	271.87000	99,504.42
206-00100	Structure Backfill (Class 1)	2,277.000	CY	60.00000	136,620.00	80.00000	182,160.00	93.58000	213,081.66
206-00360	Mechanical Reinforcement of Soil	1,209.000	CY	45.00000	54,405.00	50.00000	60,450.00	20.04000	24,228.36
206-01750	Shoring	1.000	LS	10,000.00000	10,000.00	10.00000	10.00	71,764.72000	71,764.72
206-01781	Shoring (Area 1)	1.000	LS	30,000.00000	30,000.00	50,000.00000	50,000.00	113,627.47000	113,627.47
206-01782	Shoring (Area 2)	1.000	LS	15,000.00000	15,000.00	7,000.00000	7,000.00	65,784.33000	65,784.33
206-01783	Shoring (Area 3)	1.000	LS	50,000.00000	50,000.00	7,000.00000	7,000.00	7,176.47000	7,176.47
207-00210	Stockpile Topsoil	444.000	CY	15.00000	6,660.00	11.00000	4,884.00	7.24000	3,214.56
207-00700	Topsoil (Onsite)	92.000	CY	30.00000	2,760.00	18.00000	1,656.00	25.46000	2,342.32
207-00702	Topsoil (Offsite)	352.000	CY	30.00000	10,560.00	30.00000	10,560.00	49.19000	17,314.88
207-00703	Topsoil (Wetland)	270.000	CY	30.00000	8,100.00	40.00000	10,800.00	29.02000	7,835.40

Page 3 of 33

05/20/2021

Printed On:

				(0) -EST Engineer's Es		(1) 695. KIEWI INFRASTRUCT	Г	(2) 672 OLDCASTL GROUP,	.E SW
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
207-00703	Topsoil (Wetland) (Stream Substrate)	100.000	CY	30.00000	3,000.00	45.00000	4,500.00	52.23000	5,223.00
208-00002	Erosion Log Type 1 (12 Inch)	1,726.000	LF	8.00000	13,808.00	5.50000	9,493.00	5.18000	8,940.68
208-00020	Silt Fence	200.000	LF	4.00000	800.00	2.50000	500.00	2.19000	438.00
208-00041	Rock Check Dam	9.000	EACH	1,000.00000	9,000.00	120.00000	1,080.00	618.49000	5,566.41
208-00045	Concrete Washout Structure	2.000	EACH	2,000.00000	4,000.00	1,500.00000	3,000.00	479.32000	958.64
208-00051	Storm Drain Inlet Protection (Type I)	16.000	LF	200.00000	3,200.00	12.00000	192.00	13.16000	210.56
208-00070	Vehicle Tracking Pad	2.000	EACH	2,500.00000	5,000.00	1,500.00000	3,000.00	21,165.93000	42,331.86
208-00071	Maintenance Aggregate (Vehicle Tracking Pad)	31.000	CY	70.00000	2,170.00	40.00000	1,240.00	133.42000	4,136.02
208-00103	Removal and Disposal of Sediment (Labor)	40.000	HOUR	70.00000	2,800.00	50.00000	2,000.00	67.17000	2,686.80
208-00105	Removal and Disposal of Sediment (Equipment)	40.000	HOUR	150.00000	6,000.00	150.00000	6,000.00	150.71000	6,028.40
208-00106	Sweeping (Sediment Removal)	20.000	HOUR	200.00000	4,000.00	210.00000	4,200.00	196.61000	3,932.20
208-00207	Erosion Control Management	48.000	DAY	300.00000	14,400.00	50.00000	2,400.00	347.94000	16,701.12
208-00400	Water Control	1.000	LS	60,000.00000	60,000.00	110,000.00000	110,000.00	33,430.40000	33,430.40
210-00050	Reset Fire Hydrant	1.000	EACH	8,000.00000	8,000.00	2,000.00000	2,000.00	6,045.07000	6,045.07
210-00810	Reset Ground Sign	1.000	EACH	300.00000	300.00	500.00000	500.00	538.24000	538.24

Page 4 of 33

05/20/2021

Printed On:

				(0) -EST- Engineer's Estimate		(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SW GROUP, INC.	
Item Code	Description	Quan	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
210-04010	Adjust Manhole	2.000	EACH	1,000.00000	2,000.00	2,000.00000	4,000.00	1,263.91000	2,527.82
211-03005	Dewatering	1.000	LS	25,000.00000	25,000.00	150,000.00000	150,000.00	80,735.31000	80,735.31
212-00009	Seeding (Temporary)	0.480	ACRE	5,000.00000	2,400.00	5,000.00000	2,400.00	1,886.59000	905.56
212-00032	Soil Conditioning	0.800	ACRE	5,000.00000	4,000.00	3,000.00000	2,400.00	370.31000	296.25
212-00700	Organic Fertilizer	144.000	LB	3.00000	432.00	10.00000	1,440.00	2.05000	295.20
212-00703	Humate	96.000	LB	10.00000	960.00	10.00000	960.00	1.91000	183.36
212-00708	Seeding (Native) Broadcast	0.480	ACRE	5,000.00000	2,400.00	3,000.00000	1,440.00	1,178.39000	565.63
212-00711	Seeding (Wetland) Broadcast	0.180	ACRE	10,000.00000	1,800.00	20,000.00000	3,600.00	1,782.16000	320.79
213-00002	Mulching (Weed Free Hay)	0.480	ACRE	2,000.00000	960.00	3,000.00000	1,440.00	2,922.57000	1,402.83
213-00061	Mulch Tackifier	1,320.000	LB	8.00000	10,560.00	3.50000	4,620.00	6.02000	7,946.40
214-00240	Deciduous Tree (4 Inch Caliper)	5.000	EACH	350.00000	1,750.00	1,200.00000	6,000.00	1,619.69000	8,098.45
214-01010	Brush Layer Cutting	825.000	EACH	8.00000	6,600.00	5.00000	4,125.00	2.80000	2,310.00
216-00201	Soil Retention Blanket (Straw-Coconut) (Biodegradable Class 1)	2,523.000	SY	3.00000	7,569.00	2.50000	6,307.50	3.78000	9,536.94
240-00000	Wildlife Biologist	80.000 H	HOUR	120.00000	9,600.00	150.00000	12,000.00	137.55000	11,004.00
250-00010	Environmental Health and Safety Management	1.000	LS	5,000.00000	5,000.00	4,500.00000	4,500.00	4,765.18000	4,765.18

Page 5 of 33

05/20/2021

Printed On:

			(0) -EST- Engineer's Estima			(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SW . GROUP, INC.	
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
250-00050	Monitoring Technician	40.000	HOUR	150.00000	6,000.00	160.00000	6,400.00	145.92000	5,836.80
250-00110	Health and Safety Officer	20.000	HOUR	150.00000	3,000.00	200.00000	4,000.00	209.31000	4,186.20
250-00120	Material Sampling and Delivery	10.000	EACH	600.00000	6,000.00	150.00000	1,500.00	143.53000	1,435.30
250-00200	Material Handling (Stockpile)	20.000	CY	300.00000	6,000.00	100.00000	2,000.00	129.23000	2,584.60
250-00210	Solid Waste Disposal	20.000	CY	400.00000	8,000.00	500.00000	10,000.00	137.55000	2,751.00
250-00220	Hazardous Waste Disposal	10.000	CY	400.00000	4,000.00	800.00000	8,000.00	299.02000	2,990.20
304-02000	Aggregate Base Course (Class 2)	1,192.000	TON	50.00000	59,600.00	40.00000	47,680.00	43.54000	51,899.68
304-06000	Aggregate Base Course (Class 6)	1,336.000	TON	50.00000	66,800.00	45.00000	60,120.00	38.89000	51,957.04
403-00720	Hot Mix Asphalt (Patching) (Asphalt)	1,037.000	TON	220.00000	228,140.00	250.00000	259,250.00	192.00000	199,104.00
411-10255	Emulsified Asphalt (Slow-Setting)	145.000	GAL	9.00000	1,305.00	2.00000	290.00	46.50000	6,742.50
412-00600	Concrete Pavement (6 Inch)	30.000	SY	150.00000	4,500.00	130.00000	3,900.00	178.82000	5,364.60
420-00000	Geomembrane	406.000	SY	15.00000	6,090.00	19.00000	7,714.00	11.46000	4,652.76
420-00112	Geotextile (Drainage) (Class 1)	1,183.000	SY	5.00000	5,915.00	2.50000	2,957.50	6.11000	7,228.13
504-04420	Precast Panel Facing	2,720.000	SF	55.00000	149,600.00	65.00000	176,800.00	75.84000	206,284.80
506-00212	Riprap (12 Inch)	169.000	CY	250.00000	42,250.00	250.00000	42,250.00	305.48000	51,626.12
506-00236	Riprap (36 Inch)	279.000	CY	300.00000	83,700.00	200.00000	55,800.00	257.03000	71,711.37

Page 6 of 33

05/20/2021

Printed On:

				(0) -EST- Engineer's Estimate		(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SW GROUP, INC.	
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
506-00412	Soil Riprap (12 Inch)	142.000	CY	150.00000	21,300.00	245.00000	34,790.00	297.87000	42,297.54
506-01020	Geogrid Reinforcement	1,154.000	SY	10.00000	11,540.00	5.00000	5,770.00	14.35000	16,559.90
507-00000	Concrete Slope and Ditch Paving	7.000	CY	600.00000	4,200.00	1,000.00000	7,000.00	1,176.84000	8,237.88
507-00350	Grouted Riprap Slope and Ditch Paving	154.000	CY	450.00000	69,300.00	350.00000	53,900.00	462.12000	71,166.48
515-00120	Waterproofing (Membrane)	524.000	SY	40.00000	20,960.00	30.00000	15,720.00	28.71000	15,044.04
515-00400	Concrete Sealer	87.000	SY	20.00000	1,740.00	35.00000	3,045.00	37.68000	3,278.16
601-03000	Concrete Class D	10.000	CY	1,200.00000	12,000.00	1,000.00000	10,000.00	1,052.55000	10,525.50
601-03030	Concrete Class D (Box Culvert)	34.000	CY	1,400.00000	47,600.00	1,200.00000	40,800.00	1,124.31000	38,226.54
601-03040	Concrete Class D (Bridge)	83.000	CY	1,600.00000	132,800.00	650.00000	53,950.00	1,228.37000	101,954.71
601-03050	Concrete Class D (Wall)	76.000	CY	1,400.00000	106,400.00	1,100.00000	83,600.00	1,309.72000	99,538.72
601-40300	Structural Concrete Coating	166.000	SY	30.00000	4,980.00	21.00000	3,486.00	21.53000	3,573.98
601-40400	Structural Concrete Stain	227.000	SY	15.00000	3,405.00	20.00000	4,540.00	21.53000	4,887.31
602-00000	Reinforcing Steel	7,997.000	LB	3.00000	23,991.00	3.00000	23,991.00	2.39000	19,112.83
602-00020	Reinforcing Steel (Epoxy Coated)	19,947.000	LB	3.50000	69,814.50	3.50000	69,814.50	3.59000	71,609.73
603-01180	18 Inch Reinforced Concrete Pipe	56.000	LF	125.00000	7,000.00	200.00000	11,200.00	418.93000	23,460.08
603-50012	12 Inch Plastic Pipe (SDR 35)	114.000	LF	55.00000	6,270.00	230.00000	26,220.00	106.56000	12,147.84

Page 7 of 33

05/20/2021

Printed On:

				(0) -EST- Engineer's Estimate		(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SW GROUP, INC.	
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
603-61240	24 Inch Flexible Pipe	68.000	LF	400.00000	27,200.00	180.00000	12,240.00	302.84000	20,593.12
603-71410	10x14 Ft Concrete Box Culvert (Precast)	319.000	LF	3,436.00000	1,096,084. 00	3,800.00000	1,212,200. 00	2,319.08000	739,786.52
604-14510	Inlet Special (Triple) (10 Foot)	2.000 E	EACH	15,000.00000	30,000.00	15,000.00000	30,000.00	17,144.55000	34,289.10
604-39010	Manhole Special (10 Foot)	2.000 E	EACH	10,000.00000	20,000.00	6,000.00000	12,000.00	15,107.92000	30,215.84
606-00302	Guardrail Type 3 (31 Inch Midwest Guardrail System)	44.000	LF	40.00000	1,760.00	120.00000	5,280.00	124.33000	5,470.52
606-01340	End Anchorage Type 3D	2.000 E	EACH	2,500.00000	5,000.00	1,400.00000	2,800.00	1,545.33000	3,090.66
606-01370	Transition Type 3G	2.000 E	EACH	3,000.00000	6,000.00	5,500.00000	11,000.00	5,860.79000	11,721.58
606-01380	Transition Type 3H	1.000 E	EACH	3,000.00000	3,000.00	2,100.00000	2,100.00	2,235.47000	2,235.47
606-01400	Transition Type BR10M-GR3	4.000 E	EACH	4,000.00000	16,000.00	3,500.00000	14,000.00	3,596.61000	14,386.44
606-02003	End Anchorage (Nonflared)	1.000 E	EACH	4,500.00000	4,500.00	5,300.00000	5,300.00	5,682.57000	5,682.57
606-11035	Bridge Rail Type 10 MASH	201.000	LF	250.00000	50,250.00	425.00000	85,425.00	351.71000	70,693.71
607-00005	End Post	4.000 E	EACH	350.00000	1,400.00	425.00000	1,700.00	418.63000	1,674.52
607-00010	Corner and Line Brace Post	1.000 E	EACH	600.00000	600.00	380.00000	380.00	897.06000	897.06
607-11300	Fence Combination Wire With Treated Wooden Posts	101.000	LF	25.00000	2,525.00	19.00000	1,919.00	23.92000	2,415.92
607-11525	Fence (Plastic)	500.000	LF	5.00000	2,500.00	4.00000	2,000.00	5.98000	2,990.00

Page 8 of 33

05/20/2021

Printed On:

				(0) -EST- Engineer's Estimate		(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SW GROUP, INC.	
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
608-00000	Concrete Sidewalk	236.000	SY	120.00000	28,320.00	110.00000	25,960.00	152.01000	35,874.36
608-00010	Concrete Curb Ramp	32.000	SY	175.00000	5,600.00	350.00000	11,200.00	307.16000	9,829.12
609-21020	Curb and Gutter Type 2 (Section II-B)	566.000	LF	70.00000	39,620.00	60.00000	33,960.00	68.75000	38,912.50
609-24008	Gutter Type 2 (8 Foot)	30.000	LF	90.00000	2,700.00	130.00000	3,900.00	188.07000	5,642.10
612-00001	Delineator (Type I)	6.000	EACH	30.00000	180.00	60.00000	360.00	59.80000	358.80
612-00003	Delineator (Type III)	3.000	EACH	35.00000	105.00	70.00000	210.00	71.76000	215.28
613-00200	2 Inch Electrical Conduit	1,002.000	LF	25.00000	25,050.00	21.00000	21,042.00	35.88000	35,951.76
613-04020	Hanger System	1.000	LS	40,000.00000	40,000.00	5,000.00000	5,000.00	14,532.12000	14,532.12
613-40010	Light Standard Foundation	6.000	EACH	2,000.00000	12,000.00	5,500.00000	33,000.00	3,827.45000	22,964.70
613-50210	Temporary Lighting	1.000	LS	15,000.00000	15,000.00	70,000.00000	70,000.00	17,941.18000	17,941.18
614-00011	Sign Panel (Class I)	12.000	SF	20.00000	240.00	25.00000	300.00	26.31000	315.72
614-00012	Sign Panel (Class II)	93.000	SF	25.00000	2,325.00	32.00000	2,976.00	33.49000	3,114.57
614-01512	Steel Sign Support (2-Inch Round)(Post)	24.000	LF	30.00000	720.00	18.00000	432.00	17.94000	430.56
614-01522	Steel Sign Support (2-Inch Round)(Socket)	2.000	EACH	100.00000	200.00	250.00000	500.00	239.22000	478.44
614-01575	Steel Sign Support (2-1/2 Inch Round NP-40)(Post)	115.000	LF	20.00000	2,300.00	26.00000	2,990.00	26.31000	3,025.65

Page 9 of 33

05/20/2021

Printed On:

				(0) -EST Engineer's Es		(1) 695 KIEWI INFRASTRUCT	Т	(2) 672 OLDCASTI GROUP,	LE SW
Item Code	Description	Quar	ntity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
614-01578	Steel Sign Support (2-1/2 Inch Round NP-40)(Slipbase)	9.000	EACH	300.00000	2,700.00	275.00000	2,475.00	299.02000	2,691.18
619-00007	Connect To Existing Waterline	2.000	EACH	3,000.00000	6,000.00	4,000.00000	8,000.00	2,882.38000	5,764.76
619-06120	12 Inch Ductile Iron Pipe (Class 52)	118.000	LF	300.00000	35,400.00	300.00000	35,400.00	211.03000	24,901.54
619-06125	12-Inch Ductile Iron Pipe (Preinsulated) (Class 52)	79.000	LF	500.00000	39,500.00	250.00000	19,750.00	288.43000	22,785.97
619-10180	18 Inch Welded Steel Pipe	44.000	LF	200.00000	8,800.00	200.00000	8,800.00	162.60000	7,154.40
619-75000	Cast Iron Valve Box	2.000	EACH	1,000.00000	2,000.00	400.00000	800.00	263.80000	527.60
619-75096	12 Inch Gate Valve (Mueller RWGV)	2.000	EACH	4,000.00000	8,000.00	3,000.00000	6,000.00	3,905.75000	7,811.50
620-00002	Field Office (Class 2)	1.000	EACH	30,000.00000	30,000.00	25,000.00000	25,000.00	111,074.25000	111,074.25
620-00012	Field Laboratory (Class 2)	1.000	EACH	30,000.00000	30,000.00	30,000.00000	30,000.00	113,466.41000	113,466.41
620-00020	Sanitary Facility	1.000	EACH	3,000.00000	3,000.00	7,000.00000	7,000.00	14,950.98000	14,950.98
625-00000	Construction Surveying	1.000	LS	50,000.00000	50,000.00	75,000.00000	75,000.00	53,225.50000	53,225.50
626-00000	Mobilization	1.000	LS	502,272.50000	502,272.50	510,000.00000	510,000.00	701,500.84000	701,500.84
626-01114	Public Information Management (Tier IV)	305.000	DAY	50.00000	15,250.00	65.00000	19,825.00	70.57000	21,523.85
627-00013	Pavement Marking Paint (High Build)	28.000	GAL	200.00000	5,600.00	150.00000	4,200.00	156.48000	4,381.44
627-00013	Pavement Marking Paint (High Build) (Temporary)	22.000	GAL	250.00000	5,500.00	28.00000	616.00	28.19000	620.18

Page 10 of 33

05/20/2021

Printed On:

			(0) -EST- Engineer's Estimate		(1) 695A KIEWIT INFRASTRUCTURE CO.		(2) 672A OLDCASTLE SV GROUP, INC.	
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway					LCC:		
627-30405	Preformed Thermoplastic Pavement Marking (Word-Symbol)	319.000 SF	30.00000	9,570.00	30.00000	9,570.00	32.29000	10,300.51
627-30410	Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	348.000 SF	30.00000	10,440.00	21.00000	7,308.00	22.43000	7,805.64
630-00000	Flagging	6,000.000 HOUR	26.00000	156,000.00	32.00000	192,000.00	33.49000	200,940.00
630-00007	Traffic Control Inspection	90.000 DAY	300.00000	27,000.00	240.00000	21,600.00	233.24000	20,991.60
630-00012	Traffic Control Management	195.000 DAY	900.00000	175,500.00	950.00000	185,250.00	1,010.69000	197,084.55
630-80335	Barricade (Type 3 M-A) (Temporary)	9.000 EACH	200.00000	1,800.00	350.00000	3,150.00	299.02000	2,691.18
630-80340	Pedestrian Barricade (ADA)	48.000 LF	25.00000	1,200.00	60.00000	2,880.00	59.80000	2,870.40
630-80341	Construction Traffic Sign (Panel Size A)	52.000 EACH	60.00000	3,120.00	45.00000	2,340.00	47.84000	2,487.68
630-80342	Construction Traffic Sign (Panel Size B)	12.000 EACH	60.00000	720.00	65.00000	780.00	71.76000	861.12
630-80355	Portable Message Sign Panel	2.000 EACH	5,000.00000	10,000.00	7,500.00000	15,000.00	7,176.47000	14,352.94
630-80357	Advance Warning Flashing or Sequencing Arrow Panel (B Type)	2.000 EACH	2,000.00000	4,000.00	1,800.00000	3,600.00	1,794.12000	3,588.24
630-80360	Drum Channelizing Device	70.000 EACH	25.00000	1,750.00	35.00000	2,450.00	35.88000	2,511.60
630-80363	Drum Channelizing Device (With Light) (Flashing)	2.000 EACH	50.00000	100.00	60.00000	120.00	59.80000	119.60
630-80370	Barrier (Temporary) (Concrete)	560.000 LF	50.00000	28,000.00	70.00000	39,200.00	67.85000	37,996.00
630-80380	Traffic Cone	100.000 EACH	10.00000	1,000.00	10.00000	1,000.00	5.98000	598.00

Colorado Department Of Transportation

Tabulation of Bids

Page 11 of 33

05/20/2021

Printed On:

		(0) -EST- Engineer's Estimate	(1) 695A KIEWIT INFRASTRUCTURE CO.	(2) 672A OLDCASTLE SW GROUP, INC.
Item Code Description	Quantity	Unit Price Amoun	t Unit Price Amount	Unit Price Amount
SECTION: 0001 Roadway			LCC:	
630-85006 Impact Attenuator (Sand Filled Plastic Barrel) (Temporary)	4.000 EACH	4,000.00000 16,000	7,500.00000 30,000.00	7,176.47000 28,705.88
Section Totals:		\$5,442,678.00	\$5,353,935.50	\$5,497,330.56
Contract Grand Totals		\$5,442,678.0	0 \$5,353,935.50	\$5,497,330.56

Page 12 of 33

05/20/2021

Printed On:

				(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045 WILLIAI CONSTRUG CONTRAC	MS CTION
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
201-00000	Clearing and Grubbing	1.000	LS	25,064.65000	25,064.65	175,000.00000	175,000.00	31,544.69000	31,544.69
202-00010	Removal of Tree	5.000	EACH	419.68000	2,098.40	3,500.00000	17,500.00	1,307.47000	6,537.35
202-00019	Removal of Inlet	2.000	EACH	1,888.57000	3,777.14	3,500.00000	7,000.00	2,213.59000	4,427.18
202-00021	Removal of Manhole	1.000	EACH	1,573.81000	1,573.81	3,500.00000	3,500.00	8,825.81000	8,825.81
202-00035	Removal of Pipe	792.000	LF	33.57000	26,587.44	58.00000	45,936.00	94.98000	75,224.16
202-00155	Removal of Wall	18.000	LF	52.46000	944.28	580.00000	10,440.00	177.64000	3,197.52
202-00200	Removal of Sidewalk	336.000	SY	12.59000	4,230.24	17.30000	5,812.80	18.31000	6,152.16
202-00202	Removal of Gutter	42.000	LF	34.62000	1,454.04	23.10000	970.20	32.39000	1,360.38
202-00203	Removal of Curb and Gutter	605.000	LF	14.43000	8,730.15	17.30000	10,466.50	18.23000	11,029.15
202-00220	Removal of Asphalt Mat	4,477.000	SY	7.24000	32,413.48	11.50000	51,485.50	14.01000	62,722.77
202-00250	Removal of Pavement Marking	1,418.000	SF	2.85000	4,041.30	3.20000	4,537.60	10.52000	14,917.36
202-00810	Removal of Ground Sign	6.000	EACH	209.84000	1,259.04	233.00000	1,398.00	330.32000	1,981.92
202-01000	Removal of Fence	188.000	LF	4.20000	789.60	11.50000	2,162.00	10.81000	2,032.28
203-00000	Unclassified Excavation	11,609.000	CY	29.38000	341,072.42	35.00000	406,315.00	14.38000	166,937.42
203-00400	Rock Excavation	4,775.000	CY	49.15000	234,691.25	35.00000	167,125.00	40.62000	193,960.50

Page 13 of 33

05/20/2021

Printed On:

			(3) 1415A RALPH L. WADSWO CONSTRUCTION C LLC		SWORTH Lobato Construction			(5) 045 WILLIAI CONSTRUC CONTRAC	MS CTION
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
203-01500	Blading	80.000 ⊦	IOUR	157.34000	12,587.20	115.00000	9,200.00	162.52000	13,001.60
203-01510	Backhoe	40.000 ⊦	IOUR	92.94000	3,717.60	115.00000	4,600.00	128.67000	5,146.80
203-01597	Potholing	80.000 ⊦	IOUR	284.27000	22,741.60	350.00000	28,000.00	333.11000	26,648.80
203-01622	Sweeping (With Pickup Broom)	20.000 H	IOUR	3,714.31000	74,286.20	200.00000	4,000.00	217.48000	4,349.60
203-02330	Laborer	40.000 H	IOUR	37.24000	1,489.60	61.00000	2,440.00	67.53000	2,701.20
206-00000	Structure Excavation	3,586.000	CY	38.39000	137,666.54	40.00000	143,440.00	21.15000	75,843.90
206-00065	Structure Backfill (Flow-Fill)	366.000	CY	245.92000	90,006.72	241.00000	88,206.00	219.45000	80,318.70
206-00100	Structure Backfill (Class 1)	2,277.000	CY	72.79000	165,742.83	89.00000	202,653.00	61.12000	139,170.24
206-00360	Mechanical Reinforcement of Soil	1,209.000	CY	36.44000	44,055.96	6.00000	7,254.00	22.50000	27,202.50
206-01750	Shoring	1.000	LS	120,310.30000	120,310.30	1.00000	1.00	158,470.15000	158,470.15
206-01781	Shoring (Area 1)	1.000	LS	168,938.14000	168,938.14	110,000.00000	110,000.00	52,748.71000	52,748.71
206-01782	Shoring (Area 2)	1.000	LS	30,078.93000	30,078.93	70,000.00000	70,000.00	52,748.71000	52,748.71
206-01783	Shoring (Area 3)	1.000	LS	69,132.80000	69,132.80	85,000.00000	85,000.00	103,369.95000	103,369.95
207-00210	Stockpile Topsoil	444.000	CY	8.39000	3,725.16	11.50000	5,106.00	16.96000	7,530.24
207-00700	Topsoil (Onsite)	92.000	CY	13.12000	1,207.04	11.50000	1,058.00	25.93000	2,385.56

Page 14 of 33

05/20/2021

Printed On:

		(3) 1415A RALPH L. WADSWORTH			(4) 1567 Lobato Cons		(5) 045A WILLIAMS		
					ON CO.,	LLC	,	CONSTRUC	CTION
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
207-00702	Topsoil (Offsite)	352.000	CY	13.72000	4,829.44	40.00000	14,080.00	141.42000	49,779.84
207-00703	Topsoil (Wetland)	270.000	CY	17.89000	4,830.30	40.00000	10,800.00	23.76000	6,415.20
207-00703	Topsoil (Wetland) (Stream Substrate)	100.000	CY	24.14000	2,414.00	40.00000	4,000.00	53.46000	5,346.00
208-00002	Erosion Log Type 1 (12 Inch)	1,726.000	LF	4.54000	7,836.04	4.50000	7,767.00	6.66000	11,495.16
208-00020	Silt Fence	200.000	LF	3.29000	658.00	1.70000	340.00	3.10000	620.00
208-00041	Rock Check Dam	9.000	EACH	933.79000	8,404.11	620.00000	5,580.00	2,176.83000	19,591.47
208-00045	Concrete Washout Structure	2.000	EACH	1,888.57000	3,777.14	2,080.00000	4,160.00	481.86000	963.72
208-00051	Storm Drain Inlet Protection (Type I)	16.000	LF	11.54000	184.64	11.50000	184.00	13.23000	211.68
208-00070	Vehicle Tracking Pad	2.000	EACH	2,776.39000	5,552.78	2,610.00000	5,220.00	4,907.64000	9,815.28
208-00071	Maintenance Aggregate (Vehicle Tracking Pad)	31.000	CY	156.80000	4,860.80	120.00000	3,720.00	119.89000	3,716.59
208-00103	Removal and Disposal of Sediment (Labor)	40.000	HOUR	138.57000	5,542.80	78.00000	3,120.00	81.14000	3,245.60
208-00105	Removal and Disposal of Sediment (Equipment)	40.000	HOUR	61.44000	2,457.60	201.00000	8,040.00	151.50000	6,060.00
208-00106	Sweeping (Sediment Removal)	20.000	HOUR	80.31000	1,606.20	200.00000	4,000.00	195.17000	3,903.40
208-00207	Erosion Control Management	48.000	DAY	304.27000	14,604.96	150.00000	7,200.00	394.70000	18,945.60
208-00400	Water Control	1.000	LS	70,458.44000	70,458.44	200,000.00000	200,000.00	271,191.94000	271,191.94

Page 15 of 33

05/20/2021

Printed On:

				(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045 WILLIAI CONSTRUG CONTRAC	MS CTION
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
210-00050	Reset Fire Hydrant	1.000	EACH	6,384.40000	6,384.40	8,100.00000	8,100.00	9,822.38000	9,822.38
210-00810	Reset Ground Sign	1.000	EACH	472.14000	472.14	520.00000	520.00	615.64000	615.64
210-04010	Adjust Manhole	2.000	EACH	1,096.42000	2,192.84	2,310.00000	4,620.00	1,422.10000	2,844.20
211-03005	Dewatering	1.000	LS	140,014.41000	140,014.41	175,000.00000	175,000.00	111,629.23000	111,629.23
212-00009	Seeding (Temporary)	0.480	ACRE	1,654.92000	794.36	1,230.00000	590.40	8,316.71000	3,992.02
212-00032	Soil Conditioning	0.800	ACRE	324.83000	259.86	850.00000	680.00	372.28000	297.82
212-00700	Organic Fertilizer	144.000	LB	1.79000	257.76	1.90000	273.60	2.06000	296.64
212-00703	Humate	96.000	LB	1.68000	161.28	1.20000	115.20	1.92000	184.32
212-00708	Seeding (Native) Broadcast	0.480	ACRE	1,033.69000	496.17	1,650.00000	792.00	1,184.63000	568.62
212-00711	Seeding (Wetland) Broadcast	0.180	ACRE	1,563.31000	281.40	1,400.00000	252.00	1,791.56000	322.48
213-00002	Mulching (Weed Free Hay)	0.480	ACRE	2,563.69000	1,230.57	1,530.00000	734.40	3,366.63000	1,615.98
213-00061	Mulch Tackifier	1,320.000	LB	5.28000	6,969.60	1.10000	1,452.00	11.64000	15,364.80
214-00240	Deciduous Tree (4 Inch Caliper)	5.000 I	EACH	1,420.80000	7,104.00	820.00000	4,100.00	1,807.93000	9,039.65
214-01010	Brush Layer Cutting	825.000 l	EACH	2.45000	2,021.25	10.90000	8,992.50	3.94000	3,250.50
216-00201	Soil Retention Blanket (Straw-Coconut) (Biodegradable Class 1)	2,523.000	SY	3.31000	8,351.13	3.30000	8,325.90	4.25000	10,722.75

Page 16 of 33

05/20/2021

Printed On:

			(3) 1415	A	(4) 1567	7A	(5) 045A	
			RALPH L. WADSWORTH CONSTRUCTION CO., LLC		Lobato Construction, LLC		WILLIAI CONSTRUC CONTRAC	MS CTION
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway					LCC:		
240-00000	Wildlife Biologist	80.000 HOUR	136.40000	10,912.00	370.00000	29,600.00	195.24000	15,619.20
250-00010		1.000 LS	4,180.03000	4,180.03	4,500.00000	4,500.00	16,228.94000	16,228.94
250-00050	Management Monitoring Technician	40.000 HOUR	128.00000	5,120.00	244.00000	9,760.00	168.34000	6,733.60
250-00110	Health and Safety Officer	20.000 HOUR	183.61000	3,672.20	380.00000	7,600.00	144.29000	2,885.80
250-00120	Material Sampling and Delivery	10.000 EACH	125.90000	1,259.00	137.00000	1,370.00	390.78000	3,907.80
250-00200	Material Handling (Stockpile)	20.000 CY	409.19000	8,183.80	57.00000	1,140.00	122.85000	2,457.00
250-00210	Solid Waste Disposal	20.000 CY	120.66000	2,413.20	188.00000	3,760.00	320.75000	6,415.00
250-00220	Hazardous Waste Disposal	10.000 CY	262.30000	2,623.00	340.00000	3,400.00	801.71000	8,017.10
304-02000	Aggregate Base Course (Class 2)	1,192.000 TON	41.97000	50,028.24	58.00000	69,136.00	41.22000	49,134.24
304-06000	Aggregate Base Course (Class 6)	1,336.000 TON	41.97000	56,071.92	60.00000	80,160.00	43.62000	58,276.32
403-00720	Hot Mix Asphalt (Patching) (Asphalt)	1,037.000 TON	207.49000	215,167.13	221.00000	229,177.00	250.31000	259,571.47
411-10255	Emulsified Asphalt (Slow-Setting)	145.000 GAL	50.25000	7,286.25	54.00000	7,830.00	63.28000	9,175.60
412-00600	Concrete Pavement (6 Inch)	30.000 SY	72.87000	2,186.10	112.00000	3,360.00	135.21000	4,056.30
420-00000	Geomembrane	406.000 SY	27.28000	11,075.68	17.30000	7,023.80	35.43000	14,384.58
420-00112	Geotextile (Drainage) (Class 1)	1,183.000 SY	9.44000	11,167.52	11.50000	13,604.50	8.53000	10,090.99

Page 17 of 33

05/20/2021

Printed On:

				(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045A WILLIAMS CONSTRUCTION CONTRACTORS	
Item Code	Description	Quanti	tv	Unit Price	Amount	Unit Price	Amount		Amount
		Quanti	Ly	Office Price	Amount	Office Price		Office	Amount
SECTION:	0001 Roadway						LCC:		
504-04420	Precast Panel Facing	2,720.000	SF	57.41000	156,155.20	58.00000	157,760.00	143.96000	391,571.20
506-00212	Riprap (12 Inch)	169.000	CY	183.61000	31,030.09	202.00000	34,138.00	284.75000	48,122.75
506-00236	Riprap (36 Inch)	279.000	CY	188.86000	52,691.94	231.00000	64,449.00	283.73000	79,160.67
506-00412	Soil Riprap (12 Inch)	142.000	CY	194.10000	27,562.20	231.00000	32,802.00	300.55000	42,678.10
506-01020	Geogrid Reinforcement	1,154.000	SY	6.82000	7,870.28	17.30000	19,964.20	12.21000	14,090.34
507-00000	Concrete Slope and Ditch Paving	7.000	CY	502.62000	3,518.34	1,010.00000	7,070.00	1,024.13000	7,168.91
507-00350	Grouted Riprap Slope and Ditch Paving	154.000	CY	141.37000	21,770.98	520.00000	80,080.00	576.64000	88,802.56
515-00120	Waterproofing (Membrane)	524.000	SY	30.03000	15,735.72	47.00000	24,628.00	87.12000	45,650.88
515-00400	Concrete Sealer	87.000	SY	45.38000	3,948.06	74.00000	6,438.00	82.47000	7,174.89
601-03000	Concrete Class D	10.000	CY	478.54000	4,785.40	1,000.00000	10,000.00	1,321.48000	13,214.80
601-03030	Concrete Class D (Box Culvert)	34.000	CY	712.73000	24,232.82	1,000.00000	34,000.00	1,393.63000	47,383.42
601-03040	Concrete Class D (Bridge)	83.000	CY	665.95000	55,273.85	1,000.00000	83,000.00	1,773.49000	147,199.67
601-03050	Concrete Class D (Wall)	76.000	CY	542.77000	41,250.52	1,000.00000	76,000.00	1,798.84000	136,711.84
601-40300	Structural Concrete Coating	166.000	SY	25.93000	4,304.38	34.00000	5,644.00	18.04000	2,994.64
601-40400	Structural Concrete Stain	227.000	SY	25.93000	5,886.11	34.00000	7,718.00	34.02000	7,722.54

Page 18 of 33

05/20/2021

Printed On:

	•								
				(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045 WILLIAI CONSTRUC CONTRAC	MS CTION
Item Code	Description	Quar	ntity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
602-00000	Reinforcing Steel	7,997.000	LB	2.62000	20,952.14	1.25000	9,996.25	2.58000	20,632.26
602-00020	Reinforcing Steel (Epoxy Coated)	19,947.000	LB	2.62000	52,261.14	1.50000	29,920.50	3.79000	75,599.13
603-01180	18 Inch Reinforced Concrete Pipe	56.000	LF	236.07000	13,219.92	173.00000	9,688.00	168.95000	9,461.20
603-50012	12 Inch Plastic Pipe (SDR 35)	114.000	LF	210.46000	23,992.44	173.00000	19,722.00	162.36000	18,509.04
603-61240	24 Inch Flexible Pipe	68.000	LF	133.93000	9,107.24	231.00000	15,708.00	197.33000	13,418.44
603-71410	10x14 Ft Concrete Box Culvert (Precast)	319.000	LF	2,386.88000	761,414.72	2,600.00000	829,400.00	2,136.10000	681,415.90
604-14510	Inlet Special (Triple) (10 Foot)	2.000	EACH	15,650.07000	31,300.14	23,100.00000	46,200.00	16,155.96000	32,311.92
604-39010	Manhole Special (10 Foot)	2.000	EACH	9,426.06000	18,852.12	11,500.00000	23,000.00	11,147.34000	22,294.68
606-00302	Guardrail Type 3 (31 Inch Midwest Guardrail System)	44.000	LF	109.07000	4,799.08	139.00000	6,116.00	145.41000	6,398.04
606-01340	End Anchorage Type 3D	2.000	EACH	1,355.57000	2,711.14	1,590.00000	3,180.00	2,002.69000	4,005.38
606-01370	Transition Type 3G	2.000	EACH	5,141.10000	10,282.20	7,600.00000	15,200.00	6,340.97000	12,681.94
606-01380	Transition Type 3H	1.000	EACH	1,960.96000	1,960.96	2,870.00000	2,870.00	2,696.47000	2,696.47
606-01400	Transition Type BR10M-GR3	4.000	EACH	3,154.95000	12,619.80	1,670.00000	6,680.00	4,064.82000	16,259.28
606-02003	End Anchorage (Nonflared)	1.000	EACH	4,984.77000	4,984.77	6,300.00000	6,300.00	6,610.99000	6,610.99
606-11035	Bridge Rail Type 10 MASH	201.000	LF	308.52000	62,012.52	500.00000	100,500.00	403.48000	81,099.48

Page 19 of 33

05/20/2021

Printed On:

		Contract ID. C18		(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045 WILLIAI CONSTRUG CONTRAC	MS CTION
Item Code	Description	Quar	itity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
607-00005	End Post	4.000	EACH	301.75000	1,207.00	330.00000	1,320.00	570.65000	2,282.60
607-00010	Corner and Line Brace Post	1.000	EACH	352.38000	352.38	390.00000	390.00	541.08000	541.08
607-11300	Fence Combination Wire With Treated Wooden Posts	101.000	LF	17.26000	1,743.26	19.10000	1,929.10	36.97000	3,733.97
607-11525	Fence (Plastic)	500.000	LF	4.72000	2,360.00	4.40000	2,200.00	4.18000	2,090.00
608-00000	Concrete Sidewalk	236.000	SY	40.90000	9,652.40	30.00000	7,080.00	109.42000	25,823.12
608-00010	Concrete Curb Ramp	32.000	SY	84.84000	2,714.88	176.00000	5,632.00	240.48000	7,695.36
609-21020	Curb and Gutter Type 2 (Section II-B)	566.000	LF	21.69000	12,276.54	41.00000	23,206.00	58.10000	32,884.60
609-24008	Gutter Type 2 (8 Foot)	30.000	LF	21.30000	639.00	104.00000	3,120.00	124.22000	3,726.60
612-00001	Delineator (Type I)	6.000	EACH	52.46000	314.76	58.00000	348.00	60.12000	360.72
612-00003	Delineator (Type III)	3.000	EACH	62.95000	188.85	70.00000	210.00	72.14000	216.42
613-00200	2 Inch Electrical Conduit	1,002.000	LF	19.44000	19,478.88	21.80000	21,843.60	25.84000	25,891.68
613-04020	Hanger System	1.000	LS	11,529.74000	11,529.74	18,400.00000	18,400.00	15,256.76000	15,256.76
613-40010	Light Standard Foundation	6.000	EACH	4,905.03000	29,430.18	5,500.00000	33,000.00	8,626.57000	51,759.42
613-50210	Temporary Lighting	1.000	LS	41,020.70000	41,020.70	50,000.00000	50,000.00	82,648.13000	82,648.13
614-00011	Sign Panel (Class I)	12.000	SF	23.08000	276.96	25.60000	307.20	26.45000	317.40

Page 20 of 33

05/20/2021

Printed On:

				(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045A WILLIAMS CONSTRUCTION CONTRACTORS	
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
614-00012	Sign Panel (Class II)	93.000	SF	29.38000	2,732.34	33.00000	3,069.00	33.67000	3,131.31
614-01512	Steel Sign Support (2-Inch Round)(Post)	24.000	LF	15.74000	377.76	17.50000	420.00	18.04000	432.96
614-01522	Steel Sign Support (2-Inch Round)(Socket)	2.000 E	EACH	209.84000	419.68	233.00000	466.00	240.48000	480.96
614-01575	Steel Sign Support (2-1/2 Inch Round NP-40)(Post)	115.000	LF	23.08000	2,654.20	25.60000	2,944.00	26.45000	3,041.75
614-01578	Steel Sign Support (2-1/2 Inch Round NP-40)(Slipbase)	9.000 E	EACH	262.30000	2,360.70	291.00000	2,619.00	300.60000	2,705.40
619-00007	Connect To Existing Waterline	2.000 E	EACH	1,573.81000	3,147.62	5,800.00000	11,600.00	2,413.76000	4,827.52
619-06120	12 Inch Ductile Iron Pipe (Class 52)	118.000	LF	210.78000	24,872.04	400.00000	47,200.00	196.95000	23,240.10
619-06125	12-Inch Ductile Iron Pipe (Preinsulated) (Class 52)	79.000	LF	329.10000	25,998.90	920.00000	72,680.00	727.42000	57,466.18
619-10180	18 Inch Welded Steel Pipe	44.000	LF	260.87000	11,478.28	1,150.00000	50,600.00	834.93000	36,736.92
619-75000	Cast Iron Valve Box	2.000 E	EACH	1,366.36000	2,732.72	1,730.00000	3,460.00	1,788.66000	3,577.32
619-75096	12 Inch Gate Valve (Mueller RWGV)	2.000 E	EACH	5,516.27000	11,032.54	5,800.00000	11,600.00	5,484.98000	10,969.96
620-00002	Field Office (Class 2)	1.000 E	EACH	43,883.84000	43,883.84	130,400.00000	130,400.00	44,488.98000	44,488.98
620-00012	Field Laboratory (Class 2)	1.000 E	EACH	92,086.01000	92,086.01	40,000.00000	40,000.00	44,488.98000	44,488.98
620-00020	Sanitary Facility	1.000 E	EACH	419.68000	419.68	7,500.00000	7,500.00	10,821.64000	10,821.64

Page 21 of 33

05/20/2021

Printed On:

				(3) 1415A RALPH L. WADSWORTH CONSTRUCTION CO., LLC		(4) 1567A Lobato Construction, LLC		(5) 045 WILLIAI CONSTRUC CONTRAC	MS CTION
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
625-00000	Construction Surveying	1.000	LS	51,482.78000	51,482.78	75,000.00000	75,000.00	51,986.80000	51,986.80
626-00000	Mobilization	1.000	LS	1,257,493. 43000	1,257,493. 43	610,000.00000	610,000.00	717,869.19000	717,869.19
626-01114	Public Information Management (Tier IV)	305.000	DAY	61.90000	18,879.50	74.00000	22,570.00	68.73000	20,962.65
627-00013	Pavement Marking Paint (High Build)	28.000	GAL	137.27000	3,843.56	152.00000	4,256.00	168.54000	4,719.12
627-00013	Pavement Marking Paint (High Build) (Temporary)	22.000	GAL	24.73000	544.06	27.50000	605.00	39.57000	870.54
627-30405	Preformed Thermoplastic Pavement Marking (Word-Symbol)	319.000	SF	28.33000	9,037.27	31.00000	9,889.00	35.28000	11,254.32
627-30410	Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	348.000	SF	19.67000	6,845.16	21.80000	7,586.40	25.13000	8,745.24
630-00000	Flagging	6,000.000	HOUR	29.38000	176,280.00	33.00000	198,000.00	39.97000	239,820.00
630-00007	Traffic Control Inspection	90.000	DAY	204.60000	18,414.00	227.00000	20,430.00	279.39000	25,145.10
630-00012	Traffic Control Management	195.000	DAY	886.58000	172,883.10	980.00000	191,100.00	1,075.92000	209,804.40
630-80335	Barricade (Type 3 M-A) (Temporary)	9.000	EACH	262.30000	2,360.70	291.00000	2,619.00	360.49000	3,244.41
630-80340	Pedestrian Barricade (ADA)	48.000	LF	52.46000	2,518.08	58.00000	2,784.00	60.12000	2,885.76
630-80341	Construction Traffic Sign (Panel Size A)	52.000	EACH	41.97000	2,182.44	47.00000	2,444.00	48.10000	2,501.20
630-80342	Construction Traffic Sign (Panel Size B)	12.000	EACH	62.95000	755.40	70.00000	840.00	72.14000	865.68

Page 22 of 33

05/20/2021

Printed On:

					(4) 1567A Lobato Construction, LLC		A MS CTION TORS	
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway					LCC:		
630-80355	Portable Message Sign Panel	2.000 EACH	6,295.22000	12,590.44	7,000.00000	14,000.00	7,214.43000	14,428.86
630-80357	Advance Warning Flashing or Sequencing Arrow Panel (B Type)	2.000 EACH	1,573.81000	3,147.62	1,750.00000	3,500.00	1,803.61000	3,607.22
630-80360	Drum Channelizing Device	70.000 EACH	31.48000	2,203.60	35.00000	2,450.00	36.07000	2,524.90
630-80363	Drum Channelizing Device (With Light) (Flashing)	2.000 EACH	52.46000	104.92	58.00000	116.00	60.12000	120.24
630-80370	Barrier (Temporary) (Concrete)	560.000 LF	57.71000	32,317.60	50.00000	28,000.00	115.90000	64,904.00
630-80380	Traffic Cone	100.000 EACH	5.25000	525.00	5.80000	580.00	6.01000	601.00
630-85006	Impact Attenuator (Sand Filled Plastic Barrel) (Temporary)	4.000 EACH	3,672.21000	14,688.84	7,500.00000	30,000.00	4,208.42000	16,833.68
Section To	tals:		\$5,97	3,733.91	\$6,18	33,272.15	\$6,37	79,683.27
Contract	Grand Totals		\$5,9	73,733.91	\$6,1	83,272.15	\$6,3	379,683.27

Page 23 of 33

05/20/2021

Printed On:

				(6) 101A RMS UTILITIES, INC.					
Item Code	Description	Quar	itity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
201-00000	Clearing and Grubbing	1.000	LS	39,150.00000	39,150.00				
202-00010	Removal of Tree	5.000	EACH	350.00000	1,750.00				
202-00019	Removal of Inlet	2.000	EACH	1,500.00000	3,000.00				
202-00021	Removal of Manhole	1.000	EACH	1,500.00000	1,500.00				
202-00035	Removal of Pipe	792.000	LF	65.00000	51,480.00				
202-00155	Removal of Wall	18.000	LF	150.00000	2,700.00				
202-00200	Removal of Sidewalk	336.000	SY	20.00000	6,720.00				
202-00202	Removal of Gutter	42.000	LF	10.00000	420.00				
202-00203	Removal of Curb and Gutter	605.000	LF	10.00000	6,050.00				
202-00220	Removal of Asphalt Mat	4,477.000	SY	30.00000	134,310.00				
202-00250	Removal of Pavement Marking	1,418.000	SF	12.00000	17,016.00				
202-00810	Removal of Ground Sign	6.000	EACH	90.00000	540.00				
202-01000	Removal of Fence	188.000	LF	18.00000	3,384.00				
203-00000	Unclassified Excavation	11,609.000	CY	45.00000	522,405.00				
203-00400	Rock Excavation	4,775.000	CY	150.00000	716,250.00				
203-01500	Blading	80.000	HOUR	185.00000	14,800.00				

Page 24 of 33

05/20/2021

Printed On:

				(6) 101A RMS UTILITIE					
Item Code	Description	Quai	ntity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
203-01510	Backhoe	40.000	HOUR	145.00000	5,800.00				
203-01597	Potholing	80.000	HOUR	280.00000	22,400.00				
203-01622	Sweeping (With Pickup Broom)	20.000	HOUR	180.00000	3,600.00				
203-02330	Laborer	40.000	HOUR	85.00000	3,400.00				
206-00000	Structure Excavation	3,586.000	CY	50.00000	179,300.00				
206-00065	Structure Backfill (Flow-Fill)	366.000	CY	320.00000	117,120.00				
206-00100	Structure Backfill (Class 1)	2,277.000	CY	100.00000	227,700.00				
206-00360	Mechanical Reinforcement of Soil	1,209.000	CY	75.00000	90,675.00				
206-01750	Shoring	1.000	LS	125,000.00000	125,000.00				
206-01781	Shoring (Area 1)	1.000	LS	125,000.00000	125,000.00				
206-01782	Shoring (Area 2)	1.000	LS	125,000.00000	125,000.00				
206-01783	Shoring (Area 3)	1.000	LS	125,000.00000	125,000.00				
207-00210	Stockpile Topsoil	444.000	CY	40.00000	17,760.00				
207-00700	Topsoil (Onsite)	92.000	CY	45.00000	4,140.00				
207-00702	Topsoil (Offsite)	352.000	CY	105.00000	36,960.00				
207-00703	Topsoil (Wetland)	270.000	CY	85.00000	22,950.00				

Page 25 of 33

05/20/2021

Printed On:

				(6) 101A RMS UTILITIE					
Item Code	Description	Quanti	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
207-00703	Topsoil (Wetland) (Stream Substrate)	100.000	CY	105.00000	10,500.00				
208-00002	Erosion Log Type 1 (12 Inch)	1,726.000	LF	9.00000	15,534.00				
208-00020	Silt Fence	200.000	LF	15.00000	3,000.00				
208-00041	Rock Check Dam	9.000 E	ACH	802.00000	7,218.00				
208-00045	Concrete Washout Structure	2.000 E	ACH	5,500.00000	11,000.00				
208-00051	Storm Drain Inlet Protection (Type I)	16.000	LF	85.00000	1,360.00				
208-00070	Vehicle Tracking Pad	2.000 E	ACH	6,500.00000	13,000.00				
208-00071	Maintenance Aggregate (Vehicle Tracking Pad)	31.000	CY	165.00000	5,115.00				
208-00103	Removal and Disposal of Sediment (Labor)	40.000 H	OUR	85.00000	3,400.00				
208-00105	Removal and Disposal of Sediment (Equipment)	40.000 H	OUR	185.00000	7,400.00				
208-00106	Sweeping (Sediment Removal)	20.000 H	OUR	180.00000	3,600.00				
208-00207	Erosion Control Management	48.000	DAY	300.00000	14,400.00				
208-00400	Water Control	1.000	LS	219,000.00000	219,000.00				
210-00050	Reset Fire Hydrant	1.000 E	ACH	7,200.00000	7,200.00				
210-00810	Reset Ground Sign	1.000 E	ACH	350.00000	350.00				

Page 26 of 33

05/20/2021

Printed On:

			(6) 101A RMS UTILITIES, INC.					
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway					LCC:		
210-04010	Adjust Manhole	2.000 EACH	1,500.00000	3,000.00				
211-03005	Dewatering	1.000 LS	65,000.00000	65,000.00				
212-00009	Seeding (Temporary)	0.480 ACRE	4,800.00000	2,304.00				
212-00032	Soil Conditioning	0.800 ACRE	3,100.00000	2,480.00				
212-00700	Organic Fertilizer	144.000 LB	6.00000	864.00				
212-00703	Humate	96.000 LB	7.50000	720.00				
212-00708	Seeding (Native) Broadcast	0.480 ACRE	2,800.00000	1,344.00				
212-00711	Seeding (Wetland) Broadcast	0.180 ACRE	18,000.00000	3,240.00				
213-00002	Mulching (Weed Free Hay)	0.480 ACRE	3,200.00000	1,536.00				
213-00061	Mulch Tackifier	1,320.000 LB	5.00000	6,600.00				
214-00240	Deciduous Tree (4 Inch Caliper)	5.000 EACH	1,400.00000	7,000.00				
214-01010	Brush Layer Cutting	825.000 EACH	8.50000	7,012.50				
216-00201	Soil Retention Blanket (Straw-Coconut) (Biodegradable Class 1)	2,523.000 SY	4.00000	10,092.00				
240-00000	Wildlife Biologist	80.000 HOUR	195.00000	15,600.00				
250-00010	Environmental Health and Safety Management	1.000 LS	12,000.00000	12,000.00				

Page 27 of 33

05/20/2021

Printed On:

				(6) 101A RMS UTILITIES, INC.					
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
250-00050	Monitoring Technician	40.000 H	HOUR	130.00000	5,200.00				
250-00110	Health and Safety Officer	20.000 l	HOUR	135.00000	2,700.00				
250-00120	Material Sampling and Delivery	10.000	EACH	2,057.00000	20,570.00				
250-00200	Material Handling (Stockpile)	20.000	CY	40.00000	800.00				
250-00210	Solid Waste Disposal	20.000	CY	75.00000	1,500.00				
250-00220	Hazardous Waste Disposal	10.000	CY	350.00000	3,500.00				
304-02000	Aggregate Base Course (Class 2)	1,192.000	TON	80.00000	95,360.00				
304-06000	Aggregate Base Course (Class 6)	1,336.000	TON	85.00000	113,560.00				
403-00720	Hot Mix Asphalt (Patching) (Asphalt)	1,037.000	TON	245.00000	254,065.00				
411-10255	Emulsified Asphalt (Slow-Setting)	145.000	GAL	28.00000	4,060.00				
412-00600	Concrete Pavement (6 Inch)	30.000	SY	85.00000	2,550.00				
420-00000	Geomembrane	406.000	SY	33.00000	13,398.00				
420-00112	Geotextile (Drainage) (Class 1)	1,183.000	SY	6.50000	7,689.50				
504-04420	Precast Panel Facing	2,720.000	SF	96.30000	261,936.00				
506-00212	Riprap (12 Inch)	169.000	CY	180.00000	30,420.00				
506-00236	Riprap (36 Inch)	279.000	CY	500.00000	139,500.00				

Page 28 of 33

05/20/2021

Printed On:

				(6) 101A RMS UTILITIE					
Item Code	Description	Quant	ity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
506-00412	Soil Riprap (12 Inch)	142.000	CY	265.00000	37,630.00				
506-01020	Geogrid Reinforcement	1,154.000	SY	7.00000	8,078.00				
507-00000	Concrete Slope and Ditch Paving	7.000	CY	1,800.00000	12,600.00				
507-00350	Grouted Riprap Slope and Ditch Paving	154.000	CY	370.00000	56,980.00				
515-00120	Waterproofing (Membrane)	524.000	SY	65.00000	34,060.00				
515-00400	Concrete Sealer	87.000	SY	36.00000	3,132.00				
601-03000	Concrete Class D	10.000	CY	2,565.00000	25,650.00				
601-03030	Concrete Class D (Box Culvert)	34.000	CY	2,565.00000	87,210.00				
601-03040	Concrete Class D (Bridge)	83.000	CY	2,565.00000	212,895.00				
601-03050	Concrete Class D (Wall)	76.000	CY	2,565.00000	194,940.00				
601-40300	Structural Concrete Coating	166.000	SY	36.00000	5,976.00				
601-40400	Structural Concrete Stain	227.000	SY	27.00000	6,129.00				
602-00000	Reinforcing Steel	7,997.000	LB	3.37000	26,949.89				
602-00020	Reinforcing Steel (Epoxy Coated)	19,947.000	LB	4.25000	84,774.75				
603-01180	18 Inch Reinforced Concrete Pipe	56.000	LF	175.00000	9,800.00				
603-50012	12 Inch Plastic Pipe (SDR 35)	114.000	LF	120.00000	13,680.00				

Page 29 of 33

05/20/2021

Printed On:

			(6) 101A RMS UTILITIES, INC.					
Item Code	Description	Quantity	Unit Price	Amount	Unit Price Am	ount	Unit Price	Amount
SECTION:	0001 Roadway				LC	CC:		
603-61240	24 Inch Flexible Pipe	68.000 LF	140.00000	9,520.00				
603-71410	10x14 Ft Concrete Box Culvert (Precast)	319.000 LF	3,900.00000	1,244,100. 00				
604-14510	Inlet Special (Triple) (10 Foot)	2.000 EACH	19,270.00000	38,540.00				
604-39010	Manhole Special (10 Foot)	2.000 EACH	15,500.00000	31,000.00				
606-00302	Guardrail Type 3 (31 Inch Midwest Guardrail System)	44.000 LF	185.00000	8,140.00				
606-01340	End Anchorage Type 3D	2.000 EACH	6,500.00000	13,000.00				
606-01370	Transition Type 3G	2.000 EACH	12,500.00000	25,000.00				
606-01380	Transition Type 3H	1.000 EACH	4,600.00000	4,600.00				
606-01400	Transition Type BR10M-GR3	4.000 EACH	6,500.00000	26,000.00				
606-02003	End Anchorage (Nonflared)	1.000 EACH	8,500.00000	8,500.00				
606-11035	Bridge Rail Type 10 MASH	201.000 LF	457.00000	91,857.00				
607-00005	End Post	4.000 EACH	2,500.00000	10,000.00				
607-00010	Corner and Line Brace Post	1.000 EACH	1,500.00000	1,500.00				
607-11300	Fence Combination Wire With Treated Wooden Posts	101.000 LF	65.00000	6,565.00				
607-11525	Fence (Plastic)	500.000 LF	9.50000	4,750.00				

Page 30 of 33

05/20/2021

Printed On:

				(6) 101A RMS UTILITIES, INC.					
Item Code	Description	Quan	tity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway						LCC:		
608-00000	Concrete Sidewalk	236.000	SY	72.00000	16,992.00				
608-00010	Concrete Curb Ramp	32.000	SY	322.00000	10,304.00				
609-21020	Curb and Gutter Type 2 (Section II-B)	566.000	LF	24.00000	13,584.00				
609-24008	Gutter Type 2 (8 Foot)	30.000	LF	84.00000	2,520.00				
612-00001	Delineator (Type I)	6.000	EACH	120.00000	720.00				
612-00003	Delineator (Type III)	3.000	EACH	115.00000	345.00				
613-00200	2 Inch Electrical Conduit	1,002.000	LF	39.60000	39,679.20				
613-04020	Hanger System	1.000	LS	65,000.00000	65,000.00				
613-40010	Light Standard Foundation	6.000	EACH	6,545.00000	39,270.00				
613-50210	Temporary Lighting	1.000	LS	64,500.00000	64,500.00				
614-00011	Sign Panel (Class I)	12.000	SF	48.00000	576.00				
614-00012	Sign Panel (Class II)	93.000	SF	72.00000	6,696.00				
614-01512	Steel Sign Support (2-Inch Round)(Post)	24.000	LF	30.00000	720.00				
614-01522	Steel Sign Support (2-Inch Round)(Socket)	2.000	EACH	185.00000	370.00				
614-01575	Steel Sign Support (2-1/2 Inch Round NP-40)(Post)	115.000	LF	48.00000	5,520.00				

Page 31 of 33

05/20/2021

Printed On:

			(6) 101A RMS UTILITIE					
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway					LCC:		
614-01578	Steel Sign Support (2-1/2 Inch Round NP-40)(Slipbase)	9.000 EACH	600.00000	5,400.00				
619-00007	Connect To Existing Waterline	2.000 EACH	11,000.00000	22,000.00				
619-06120	12 Inch Ductile Iron Pipe (Class 52)	118.000 LF	190.00000	22,420.00				
619-06125	12-Inch Ductile Iron Pipe (Preinsulated) (Class 52)	79.000 LF	284.00000	22,436.00				
619-10180	18 Inch Welded Steel Pipe	44.000 LF	720.00000	31,680.00				
619-75000	Cast Iron Valve Box	2.000 EACH	750.00000	1,500.00				
619-75096	12 Inch Gate Valve (Mueller RWGV)	2.000 EACH	7,050.00000	14,100.00				
620-00002	Field Office (Class 2)	1.000 EACH	88,000.00000	88,000.00				
620-00012	Field Laboratory (Class 2)	1.000 EACH	35,000.00000	35,000.00				
620-00020	Sanitary Facility	1.000 EACH	3,600.00000	3,600.00				
625-00000	Construction Surveying	1.000 LS	28,500.00000	28,500.00				
626-00000	Mobilization	1.000 LS	450,000.00000	450,000.00				
626-01114	Public Information Management (Tier IV)	305.000 DAY	103.00000	31,415.00				
627-00013	Pavement Marking Paint (High Build)	28.000 GAL	210.00000	5,880.00				
627-00013	Pavement Marking Paint (High Build) (Temporary)	22.000 GAL	160.00000	3,520.00				

Page 32 of 33

05/20/2021

Printed On:

			(6) 101A RMS UTILITIES					
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 Roadway					LCC:		
627-30405	Preformed Thermoplastic Pavement Marking (Word-Symbol)	319.000 SF	48.00000	15,312.00				
627-30410	Preformed Thermoplastic Pavement Marking (Xwalk-Stop Line)	348.000 SF	35.00000	12,180.00				
630-00000	Flagging	6,000.000 HOUR	42.15000 2	252,900.00				
630-00007	Traffic Control Inspection	90.000 DAY	1,050.00000	94,500.00				
630-00012	Traffic Control Management	195.000 DAY	1,050.00000 2	204,750.00				
630-80335	Barricade (Type 3 M-A) (Temporary)	9.000 EACH	102.00000	918.00				
630-80340	Pedestrian Barricade (ADA)	48.000 LF	50.00000	2,400.00				
630-80341	Construction Traffic Sign (Panel Size A)	52.000 EACH	45.00000	2,340.00				
630-80342	Construction Traffic Sign (Panel Size B)	12.000 EACH	65.00000	780.00				
630-80355	Portable Message Sign Panel	2.000 EACH	14,500.00000	29,000.00				
630-80357	Advance Warning Flashing or Sequencing Arrow Panel (B Type)	2.000 EACH	2,500.00000	5,000.00				
630-80360	Drum Channelizing Device	70.000 EACH	35.00000	2,450.00				
630-80363	Drum Channelizing Device (With Light) (Flashing)	2.000 EACH	48.00000	96.00				
630-80370	Barrier (Temporary) (Concrete)	560.000 LF	100.00000	56,000.00				
630-80380	Traffic Cone	100.000 EACH	10.00000	1,000.00				

Colorado Department Of Transportation

Tabulation of Bids

Page 33 of 33

05/20/2021

Printed On:

		(6) 101A RMS UTILITIES, INC.		
Item Code Description	Quantity	Unit Price Amount	Unit Price Amount	Unit Price Amount
SECTION: 0001 Roadway			LCC:	
630-85006 Impact Attenuator (Sand Filled Plastic Barrel) (Temporary)	4.000 EACH	3,375.00000 13,500.00		
Section Totals:		\$8,239,887.84		
Contract Grand Totals		\$8,239,887.84		

Colorado Department Of Transportation

Low Bid Item Analysis

Page 1 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0005	201-00000 Clearing and Gru	1.000 bbing	40,000.00000	20,000.00000 L S	40,000.00	20,000.00	50.00%	-20,000.00
0010	202-00010 Removal of Tree	5.000	250.00000	1,000.00000 EACH	1,250.00	5,000.00	400.00%	3,750.00
0015	202-00019 Removal of Inlet	2.000	2,000.00000	2,000.00000 EACH	4,000.00	4,000.00	100.00%	0.00
0020	202-00021 Removal of Manh	1.000 nole	2,500.00000	2,500.00000 EACH	2,500.00	2,500.00	100.00%	0.00
0025	202-00035 Removal of Pipe	792.000	40.00000	45.00000 LF	31,680.00	35,640.00	112.50%	3,960.00
0030	202-00155 Removal of Wall	18.000	150.00000	110.00000 LF	2,700.00	1,980.00	73.33%	-720.00
0035	202-00200 Removal of Sidev	336.000 valk	40.00000	25.00000 SY	13,440.00	8,400.00	62.50%	-5,040.00
0040	202-00202 Removal of Gutte	42.000 er	30.00000	60.00000 LF	1,260.00	2,520.00	200.00%	1,260.00
0045	202-00203 Removal of Curb	605.000 and Gutter	20.00000	20.00000 LF	12,100.00	12,100.00	100.00%	0.00
0050	202-00220 Removal of Asph	4,477.000 alt Mat	15.00000	6.00000 SY	67,155.00	26,862.00	40.00%	-40,293.00
0055	202-00250 Removal of Pave	1,418.000 ment Marking	5.00000	3.00000 SF	7,090.00	4,254.00	60.00%	-2,836.00
0060	202-00810 Removal of Grou	6.000 nd Sign	150.00000	250.00000 EACH	900.00	1,500.00	166.67%	600.00

Low Bid Item Analysis

Page 2 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0065	202-01000 Removal of Fend	188.000 ce	4.00000	11.00000 LF	752.00	2,068.00	275.00%	1,316.00
0070	203-00000 Unclassified Exc	11,609.000 avation	25.00000	12.00000 CY	290,225.00	139,308.00	48.00%	-150,917.00
0075	203-00400 Rock Excavation	4,775.000	70.00000	30.00000 CY	334,250.00	143,250.00	42.86%	-191,000.00
0800	203-01500 Blading	80.000	150.00000	160.00000 HOUR	12,000.00	12,800.00	106.67%	800.00
0085	203-01510 Backhoe	40.000	150.00000	140.00000 HOUR	6,000.00	5,600.00	93.33%	-400.00
0090	203-01597 Potholing	80.000	250.00000	400.00000 HOUR	20,000.00	32,000.00	160.00%	12,000.00
0095	203-01622 Sweeping (With	20.000 Pickup Broom)	200.00000	250.00000 HOUR	4,000.00	5,000.00	125.00%	1,000.00
0100	203-02330 Laborer	40.000	60.00000	50.00000 HOUR	2,400.00	2,000.00	83.33%	-400.00
0105	206-00000 Structure Excava	3,586.000 ation	30.00000	20.00000 CY	107,580.00	71,720.00	66.67%	-35,860.00
0110	206-00065 Structure Backfil	366.000 I (Flow-Fill)	230.00000	300.00000 CY	84,180.00	109,800.00	130.43%	25,620.00
0115	206-00100 Structure Backfil	2,277.000 I (Class 1)	60.00000	80.00000 CY	136,620.00	182,160.00	133.33%	45,540.00
0120	206-00360 Mechanical Rein	1,209.000 forcement of Soil	45.00000	50.00000 CY	54,405.00	60,450.00	111.11%	6,045.00

Low Bid Item Analysis

Printed On: **05/20/2021**Page 3 of 14

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0125	206-01750 Shoring	1.000	10,000.00000	10.00000 L S	10,000.00	10.00	0.10%	-9,990.00
0130	206-01781 Shoring (Area 1)	1.000	30,000.00000	50,000.00000 L S	30,000.00	50,000.00	166.67%	20,000.00
0135	206-01782 Shoring (Area 2)	1.000	15,000.00000	7,000.00000 L S	15,000.00	7,000.00	46.67%	-8,000.00
0140	206-01783 Shoring (Area 3)	1.000	50,000.00000	7,000.00000 L S	50,000.00	7,000.00	14.00%	-43,000.00
0145	207-00210 Stockpile Topsoil	444.000	15.00000	11.00000 CY	6,660.00	4,884.00	73.33%	-1,776.00
0150	207-00700 Topsoil (Onsite)	92.000	30.00000	18.00000 CY	2,760.00	1,656.00	60.00%	-1,104.00
0155	207-00702 Topsoil (Offsite)	352.000	30.00000	30.00000 CY	10,560.00	10,560.00	100.00%	0.00
0160	207-00703 Topsoil (Wetland)	270.000	30.00000	40.00000 CY	8,100.00	10,800.00	133.33%	2,700.00
0165	207-00703 Topsoil (Wetland)	100.000 (Stream Substrate)	30.00000	45.00000 CY	3,000.00	4,500.00	150.00%	1,500.00
0170	208-00002 Erosion Log Type	1,726.000 1 (12 Inch)	8.00000	5.50000 LF	13,808.00	9,493.00	68.75%	-4,315.00
0175	208-00020 Silt Fence	200.000	4.00000	2.50000 LF	800.00	500.00	62.50%	-300.00
0180	208-00041 Rock Check Dam	9.000	1,000.00000	120.00000 EACH	9,000.00	1,080.00	12.00%	-7,920.00

Low Bid Item Analysis

Printed On: **05/20/2021**Page 4 of 14

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0185	208-00045 Concrete Washo	2.000 out Structure	2,000.00000	1,500.00000 EACH	4,000.00	3,000.00	75.00%	-1,000.00
0190	208-00051 Storm Drain Inle	16.000 t Protection (Type	200.00000 I)	12.00000 LF	3,200.00	192.00	6.00%	-3,008.00
0195	208-00070 Vehicle Tracking	2.000 Pad	2,500.00000	1,500.00000 EACH	5,000.00	3,000.00	60.00%	-2,000.00
0200	208-00071 Maintenance Ag	31.000 gregate (Vehicle T	70.00000 racking Pad)	40.00000 CY	2,170.00	1,240.00	57.14%	-930.00
0205	208-00103 Removal and Dis	40.000 sposal of Sedimen	70.00000 t (Labor)	50.00000 HOUR	2,800.00	2,000.00	71.43%	-800.00
0210	208-00105 Removal and Dis	40.000 sposal of Sedimen	150.00000 t (Equipment)	150.00000 HOUR	6,000.00	6,000.00	100.00%	0.00
0215	208-00106 Sweeping (Sedir	20.000 ment Removal)	200.00000	210.00000 HOUR	4,000.00	4,200.00	105.00%	200.00
0220	208-00207 Erosion Control	48.000 Management	300.00000	50.00000 DAY	14,400.00	2,400.00	16.67%	-12,000.00
0225	208-00400 Water Control	1.000	60,000.00000	110,000.00000 L S	60,000.00	110,000.00	183.33%	50,000.00
0230	210-00050 Reset Fire Hydra	1.000 ant	8,000.00000	2,000.00000 EACH	8,000.00	2,000.00	25.00%	-6,000.00
0235	210-00810 Reset Ground S	1.000 ign	300.00000	500.00000 EACH	300.00	500.00	166.67%	200.00
0240	210-04010 Adjust Manhole	2.000	1,000.00000	2,000.00000 EACH	2,000.00	4,000.00	200.00%	2,000.00

Low Bid Item Analysis

Page 5 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0245	211-03005 Dewatering	1.000	25,000.00000	150,000.00000 L S	25,000.00	150,000.00	600.00%	125,000.00
0250	212-00009 Seeding (Tempo	0.480 rary)	5,000.00000	5,000.00000 ACRE	2,400.00	2,400.00	100.00%	0.00
0255	212-00032 Soil Conditioning	0.800	5,000.00000	3,000.00000 ACRE	4,000.00	2,400.00	60.00%	-1,600.00
0260	212-00700 Organic Fertilizer	144.000	3.00000	10.00000 LB	432.00	1,440.00	333.33%	1,008.00
0265	212-00703 Humate	96.000	10.00000	10.00000 LB	960.00	960.00	100.00%	0.00
0270	212-00708 Seeding (Native)	0.480 Broadcast	5,000.00000	3,000.00000 ACRE	2,400.00	1,440.00	60.00%	-960.00
0275	212-00711 Seeding (Wetland	0.180 d) Broadcast	10,000.00000	20,000.00000 ACRE	1,800.00	3,600.00	200.00%	1,800.00
0280	213-00002 Mulching (Weed	0.480 Free Hay)	2,000.00000	3,000.00000 ACRE	960.00	1,440.00	150.00%	480.00
0285	213-00061 Mulch Tackifier	1,320.000	8.00000	3.50000 LB	10,560.00	4,620.00	43.75%	-5,940.00
0290	214-00240 Deciduous Tree	5.000 (4 Inch Caliper)	350.00000	1,200.00000 EACH	1,750.00	6,000.00	342.86%	4,250.00
0295	214-01010 Brush Layer Cutt	825.000 ing	8.00000	5.00000 EACH	6,600.00	4,125.00	62.50%	-2,475.00
0300	216-00201 Soil Retention Bla (Biodegradable C	2,523.000 anket (Straw-Coco Class 1)	3.00000 onut)	2.50000 SY	7,569.00	6,307.50	83.33%	-1,261.50

Low Bid Item Analysis

Page 6 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0305	240-00000 Wildlife Biologist	80.000	120.00000	150.00000 HOUR	9,600.00	12,000.00	125.00%	2,400.00
0310	250-00010 Environmental H	1.000 ealth and Safety Ma	5,000.00000 anagement	4,500.00000 L S	5,000.00	4,500.00	90.00%	-500.00
0315	250-00050 Monitoring Tech	40.000 nician	150.00000	160.00000 HOUR	6,000.00	6,400.00	106.67%	400.00
0320	250-00110 Health and Safet	20.000 ry Officer	150.00000	200.00000 HOUR	3,000.00	4,000.00	133.33%	1,000.00
0325	250-00120 Material Samplin	10.000 g and Delivery	600.00000	150.00000 EACH	6,000.00	1,500.00	25.00%	-4,500.00
0330	250-00200 Material Handlin	20.000 g (Stockpile)	300.00000	100.00000 CY	6,000.00	2,000.00	33.33%	-4,000.00
0335	250-00210 Solid Waste Disp	20.000 oosal	400.00000	500.00000 CY	8,000.00	10,000.00	125.00%	2,000.00
0340	250-00220 Hazardous Wast	10.000 e Disposal	400.00000	800.00000 CY	4,000.00	8,000.00	200.00%	4,000.00
0345	304-02000 Aggregate Base	1,192.000 Course (Class 2)	50.00000	40.00000 TON	59,600.00	47,680.00	80.00%	-11,920.00
0350	304-06000 Aggregate Base	1,336.000 Course (Class 6)	50.00000	45.00000 TON	66,800.00	60,120.00	90.00%	-6,680.00
0355	403-00720 Hot Mix Asphalt	1,037.000 (Patching) (Asphalt)	220.00000	250.00000 TON	228,140.00	259,250.00	113.64%	31,110.00
0360	411-10255 Emulsified Aspha	145.000 alt (Slow-Setting)	9.00000	2.00000 GAL	1,305.00	290.00	22.22%	-1,015.00

Low Bid Item Analysis

Page 7 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0365	412-00600 Concrete Paveme	30.000 ent (6 Inch)	150.00000	130.00000 SY	4,500.00	3,900.00	86.67%	-600.00
0370	420-00000 Geomembrane	406.000	15.00000	19.00000 SY	6,090.00	7,714.00	126.67%	1,624.00
0375	420-00112 Geotextile (Draina	1,183.000 age) (Class 1)	5.00000	2.50000 SY	5,915.00	2,957.50	50.00%	-2,957.50
0380	504-04420 Precast Panel Fa	2,720.000 cing	55.00000	65.00000 SF	149,600.00	176,800.00	118.18%	27,200.00
0385	506-00212 Riprap (12 Inch)	169.000	250.00000	250.00000 CY	42,250.00	42,250.00	100.00%	0.00
0390	506-00236 Riprap (36 Inch)	279.000	300.00000	200.00000 CY	83,700.00	55,800.00	66.67%	-27,900.00
0395	506-00412 Soil Riprap (12 In	142.000 ch)	150.00000	245.00000 CY	21,300.00	34,790.00	163.33%	13,490.00
0400	506-01020 Geogrid Reinforce	1,154.000 ement	10.00000	5.00000 SY	11,540.00	5,770.00	50.00%	-5,770.00
0405	507-00000 Concrete Slope a	7.000 nd Ditch Paving	600.00000	1,000.00000 CY	4,200.00	7,000.00	166.67%	2,800.00
0410	507-00350 Grouted Riprap S	154.000 lope and Ditch Paving	450.00000	350.00000 CY	69,300.00	53,900.00	77.78%	-15,400.00
0415	515-00120 Waterproofing (M	524.000 embrane)	40.00000	30.00000 SY	20,960.00	15,720.00	75.00%	-5,240.00
0420	515-00400 Concrete Sealer	87.000	20.00000	35.00000 SY	1,740.00	3,045.00	175.00%	1,305.00

Low Bid Item Analysis

Page 8 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0425	601-03000 Concrete Class I	10.000 D	1,200.00000	1,000.00000 CY	12,000.00	10,000.00	83.33%	-2,000.00
0430	601-03030 Concrete Class I	34.000 D (Box Culvert)	1,400.00000	1,200.00000 CY	47,600.00	40,800.00	85.71%	-6,800.00
0435	601-03040 Concrete Class I	83.000 D (Bridge)	1,600.00000	650.00000 CY	132,800.00	53,950.00	40.63%	-78,850.00
0440	601-03050 Concrete Class I	76.000 O (Wall)	1,400.00000	1,100.00000 CY	106,400.00	83,600.00	78.57%	-22,800.00
0445	601-40300 Structural Concr	166.000 ete Coating	30.00000	21.00000 SY	4,980.00	3,486.00	70.00%	-1,494.00
0450	601-40400 Structural Concr	227.000 ete Stain	15.00000	20.00000 SY	3,405.00	4,540.00	133.33%	1,135.00
0455	602-00000 Reinforcing Stee	7,997.000 I	3.00000	3.00000 LB	23,991.00	23,991.00	100.00%	0.00
0460	602-00020 Reinforcing Stee	19,947.000 I (Epoxy Coated)	3.50000	3.50000 LB	69,814.50	69,814.50	100.00%	0.00
0465	603-01180 18 Inch Reinford	56.000 ed Concrete Pipe	125.00000	200.00000 LF	7,000.00	11,200.00	160.00%	4,200.00
0470	603-50012 12 Inch Plastic P	114.000 lipe (SDR 35)	55.00000	230.00000 LF	6,270.00	26,220.00	418.18%	19,950.00
0475	603-61240 24 Inch Flexible	68.000 Pipe	400.00000	180.00000 LF	27,200.00	12,240.00	45.00%	-14,960.00
0480	603-71410 10x14 Ft Concre	319.000 te Box Culvert (Pred	3,436.00000 cast)	3,800.00000 LF	1,096,084.00	1,212,200.00	110.59%	116,116.00

Low Bid Item Analysis

Page 9 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0485	604-14510 Inlet Special (Tri	2.000 ple) (10 Foot)	15,000.00000	15,000.00000 EACH	30,000.00	30,000.00	100.00%	0.00
0490	604-39010 Manhole Specia	2.000 I (10 Foot)	10,000.00000	6,000.00000 EACH	20,000.00	12,000.00	60.00%	-8,000.00
0495	606-00302 Guardrail Type 3 System)	44.000 3 (31 Inch Midwest	40.00000 Guardrail	120.00000 LF	1,760.00	5,280.00	300.00%	3,520.00
0500	606-01340 End Anchorage	2.000 Type 3D	2,500.00000	1,400.00000 EACH	5,000.00	2,800.00	56.00%	-2,200.00
0505	606-01370 Transition Type	2.000 3G	3,000.00000	5,500.00000 EACH	6,000.00	11,000.00	183.33%	5,000.00
0510	606-01380 Transition Type	1.000 3H	3,000.00000	2,100.00000 EACH	3,000.00	2,100.00	70.00%	-900.00
0515	606-01400 Transition Type	4.000 BR10M-GR3	4,000.00000	3,500.00000 EACH	16,000.00	14,000.00	87.50%	-2,000.00
0520	606-02003 End Anchorage	1.000 (Nonflared)	4,500.00000	5,300.00000 EACH	4,500.00	5,300.00	117.78%	800.00
0525	606-11035 Bridge Rail Type	201.000 10 MASH	250.00000	425.00000 LF	50,250.00	85,425.00	170.00%	35,175.00
0530	607-00005 End Post	4.000	350.00000	425.00000 EACH	1,400.00	1,700.00	121.43%	300.00
0535	607-00010 Corner and Line	1.000 Brace Post	600.00000	380.00000 EACH	600.00	380.00	63.33%	-220.00

Low Bid Item Analysis

Printed On: Page 10 of 14

05/20/2021

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0540	607-11300 Fence Combinat Posts	101.000 ion Wire With Trea	25.00000 ited Wooden	19.00000 LF	2,525.00	1,919.00	76.00%	-606.00
0545	607-11525 Fence (Plastic)	500.000	5.00000	4.00000 LF	2,500.00	2,000.00	80.00%	-500.00
0550	608-00000 Concrete Sidewa	236.000 alk	120.00000	110.00000 SY	28,320.00	25,960.00	91.67%	-2,360.00
0555	608-00010 Concrete Curb F	32.000 Ramp	175.00000	350.00000 SY	5,600.00	11,200.00	200.00%	5,600.00
0560	609-21020 Curb and Gutter	566.000 Type 2 (Section II-	70.00000 ·B)	60.00000 LF	39,620.00	33,960.00	85.71%	-5,660.00
0565	609-24008 Gutter Type 2 (8	30.000 Foot)	90.00000	130.00000 LF	2,700.00	3,900.00	144.44%	1,200.00
0570	612-00001 Delineator (Type	6.000 e I)	30.00000	60.00000 EACH	180.00	360.00	200.00%	180.00
0575	612-00003 Delineator (Type	3.000 : III)	35.00000	70.00000 EACH	105.00	210.00	200.00%	105.00
0580	613-00200 2 Inch Electrical	1,002.000 Conduit	25.00000	21.00000 LF	25,050.00	21,042.00	84.00%	-4,008.00
0585	613-04020 Hanger System	1.000	40,000.00000	5,000.00000 L S	40,000.00	5,000.00	12.50%	-35,000.00
0590	613-40010 Light Standard F	6.000 oundation	2,000.00000	5,500.00000 EACH	12,000.00	33,000.00	275.00%	21,000.00
0595	613-50210 Temporary Light	1.000 ing	15,000.00000	70,000.00000 L S	15,000.00	70,000.00	466.67%	55,000.00

Low Bid Item Analysis

Page 11 of 14

05/20/2021

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0600	614-00011 Sign Panel (Clas	12.000 ss I)	20.00000	25.00000 SF	240.00	300.00	125.00%	60.00
0605	614-00012 Sign Panel (Clas	93.000 ss II)	25.00000	32.00000 SF	2,325.00	2,976.00	128.00%	651.00
0610	614-01512 Steel Sign Suppo	24.000 ort (2-Inch Round)(30.00000 Post)	18.00000 LF	720.00	432.00	60.00%	-288.00
0615	614-01522 Steel Sign Suppo	2.000 ort (2-Inch Round)(100.00000 Socket)	250.00000 EACH	200.00	500.00	250.00%	300.00
0620	614-01575 Steel Sign Suppo 40)(Post)	115.000 ort (2-1/2 Inch Rou	20.00000 nd NP-	26.00000 LF	2,300.00	2,990.00	130.00%	690.00
0625	614-01578 Steel Sign Suppo 40)(Slipbase)	9.000 ort (2-1/2 Inch Roul	300.00000 nd NP-	275.00000 EACH	2,700.00	2,475.00	91.67%	-225.00
0630	619-00007 Connect To Exis	2.000 ting Waterline	3,000.00000	4,000.00000 EACH	6,000.00	8,000.00	133.33%	2,000.00
0635	619-06120 12 Inch Ductile I	118.000 ron Pipe (Class 52)	300.00000	300.00000 LF	35,400.00	35,400.00	100.00%	0.00
0640	619-06125 12-Inch Ductile I 52)	79.000 ron Pipe (Preinsula	500.00000 ted) (Class	250.00000 LF	39,500.00	19,750.00	50.00%	-19,750.00
0645	619-10180 18 Inch Welded	44.000 Steel Pipe	200.00000	200.00000 LF	8,800.00	8,800.00	100.00%	0.00
0650	619-75000 Cast Iron Valve I	2.000 3ox	1,000.00000	400.00000 EACH	2,000.00	800.00	40.00%	-1,200.00

Low Bid Item Analysis

Printed On: **05/20/2021**Page 12 of 14

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0655	619-75096 12 Inch Gate Val	2.000 ve (Mueller RWGV)	4,000.00000	3,000.00000 EACH	8,000.00	6,000.00	75.00%	-2,000.00
0660	620-00002 Field Office (Clas	1.000 ss 2)	30,000.00000	25,000.00000 EACH	30,000.00	25,000.00	83.33%	-5,000.00
0665	620-00012 Field Laboratory	1.000 (Class 2)	30,000.00000	30,000.00000 EACH	30,000.00	30,000.00	100.00%	0.00
0670	620-00020 Sanitary Facility	1.000	3,000.00000	7,000.00000 EACH	3,000.00	7,000.00	233.33%	4,000.00
0675	625-00000 Construction Sur	1.000 veying	50,000.00000	75,000.00000 L S	50,000.00	75,000.00	150.00%	25,000.00
0680	626-00000 Mobilization	1.000	502,272.50000	510,000.00000 L S	502,272.50	510,000.00	101.54%	7,727.50
0685	626-01114 Public Informatio	305.000 n Management (Tier	50.00000 · IV)	65.00000 DAY	15,250.00	19,825.00	130.00%	4,575.00
0690	627-00013 Pavement Markir	28.000 ng Paint (High Build)	200.00000	150.00000 GAL	5,600.00	4,200.00	75.00%	-1,400.00
0695	627-00013 Pavement Markii (Temporary)	22.000 ng Paint (High Build)	250.00000	28.00000 GAL	5,500.00	616.00	11.20%	-4,884.00
0700	627-30405 Preformed Therm (Word-Symbol)	319.000 noplastic Pavement	30.00000 Marking	30.00000 SF	9,570.00	9,570.00	100.00%	0.00
0705	627-30410 Preformed Thern (Xwalk-Stop Line	348.000 noplastic Pavement	30.00000 Marking	21.00000 SF	10,440.00	7,308.00	70.00%	-3,132.00

Low Bid Item Analysis

Printed On:

Page 13 of 14

05/20/2021

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0710	630-00000 Flagging	6,000.000	26.00000	32.00000 HOUR	156,000.00	192,000.00	123.08%	36,000.00
0715	630-00007 Traffic Control In	90.000 nspection	300.00000	240.00000 DAY	27,000.00	21,600.00	80.00%	-5,400.00
0720	630-00012 Traffic Control N	195.000 Nanagement	900.00000	950.00000 DAY	175,500.00	185,250.00	105.56%	9,750.00
0725	630-80335 Barricade (Type	9.000 3 M-A) (Temporary)	200.00000	350.00000 EACH	1,800.00	3,150.00	175.00%	1,350.00
0730	630-80340 Pedestrian Barr	48.000 icade (ADA)	25.00000	60.00000 LF	1,200.00	2,880.00	240.00%	1,680.00
0735	630-80341 Construction Tra	52.000 affic Sign (Panel Size	60.00000 e A)	45.00000 EACH	3,120.00	2,340.00	75.00%	-780.00
0740	630-80342 Construction Tra	12.000 affic Sign (Panel Size	60.00000 e B)	65.00000 EACH	720.00	780.00	108.33%	60.00
0745	630-80355 Portable Messa	2.000 ge Sign Panel	5,000.00000	7,500.00000 EACH	10,000.00	15,000.00	150.00%	5,000.00
0750	630-80357 Advance Warnir Panel (B Type)	2.000 ng Flashing or Seque	2,000.00000 encing Arrow	1,800.00000 EACH	4,000.00	3,600.00	90.00%	-400.00
0755	630-80360 Drum Channeliz	70.000 ting Device	25.00000	35.00000 EACH	1,750.00	2,450.00	140.00%	700.00
0760	630-80363 Drum Channeliz (Flashing)	2.000 ting Device (With Lig	50.00000 ht)	60.00000 EACH	100.00	120.00	120.00%	20.00

Low Bid Item Analysis

Printed On: Page 14 of 14

05/20/2021

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	Roadway						
0765	630-80370 560.000 50.00000 Barrier (Temporary) (Concrete)			70.00000 LF	28,000.00	39,200.00	140.00%	11,200.00
0770	630-80380 Traffic Cone	100.000	10.00000	10.00000 EACH	1,000.00	1,000.00	100.00%	0.00
0775	, ,			7,500.00000 EACH	16,000.00	30,000.00	187.50%	14,000.00
Section 0001 Subtotal					\$5,442,678.00	\$5,353,935.50	98.37%	-\$88,742.50
Contract Total for Calculated Low Bidders Bid Items					\$5,442,678.00	\$5,353,935.50	98.37%	-\$88,742.50