Colorado Department Of Transportation Low Bid Summary

07/23/2020Page 1 of 1

Printed On:

Letting Date: July 23, 2020

Call Order	Contract ID	Project(s)	# of Bids	Low Bidder	Estimated Cost	Corrected Bid	Percent of Estimate	Overrun (+) Underrun (-)
001	001 C22478 STMR200-249 2 Frontier Environmental S		Frontier Environmental Services, LLC	\$725,000.00	\$424,274.00	58.52%	-\$300,726.00	
Lettii	ng Totals		2		\$725,000.00	\$424,274.00	58.52%	-\$300,726.00

Vendor Ranking

Page 1 of 1

07/23/2020

Printed On:

Contract ID: C22478

Contract Description:

US 24, M.P. 288.74, will clean culvert and box culvert and repair joint between the CMP and CBC, and will add Turf Reinforcement Mat and Rock Check Dams near inlet to help prevent Erosion.

SH 115, M.P. 8.22, in Florence, will repair floor of box culvert, slip line box with 78" culvert and fill in voids with Concrete Type BZ.

SH 9, M.P. 46.63 will fill old culvert with grout and install new culvert next to existing culvert. This will require trench digging and a temporary traffic signal for traffic control with one lane closed at a time in order to install culvert. The slopes in this area will be corrected as shown in the cross sections.

Rank	Vendor ID	Vendor Name	Total Bid	Percent Of Low Bid	Percent Of Estimate
1	1721	Frontier Environmental Services, LLC	\$424,274.00	100.00%	58.52%
2	1282A	AMERICAN WEST CONSTRUCTION, LLC	\$696,485.70	164.16%	96.07%
0	-EST-	Engineer's Estimate	\$725,000.00	170.88%	100.00%

Page 1 of 5

07/23/2020

Printed On:

				(0) -EST Engineer's Es		(1) 172 Frontier Enviro Services,	onmental	(2) 1282A AMERICAN WEST CONSTRUCTION, LLC	
Item Code	Description	Qua	ntity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS						LCC:		
201-00000	Clearing and Grubbing	1.000	LS	9,600.00000	9,600.00	3,500.00000	3,500.00	12,000.00000	12,000.00
201-00007	Removal of Debris	1.000	EACH	600.00000	600.00	250.00000	250.00	290.00000	290.00
202-00010	Removal of Tree	2.000	EACH	250.00000	500.00	250.00000	500.00	290.00000	580.00
202-00150	Removal of Wall	1.000	EACH	8,000.00000	8,000.00	2,000.00000	2,000.00	3,900.00000	3,900.00
202-00220	Removal of Asphalt Mat	42.000	SY	20.00000	840.00	36.00000	1,512.00	110.00000	4,620.00
202-04008	Clean Culvert	122.000	LF	65.00000	7,930.00	45.00000	5,490.00	54.50000	6,649.00
203-00060	Embankment Material (Complete In Place)	209.000	CY	35.00000	7,315.00	52.00000	10,868.00	87.50000	18,287.50
203-01500	Blading	20.000	HOUR	250.00000	5,000.00	125.00000	2,500.00	240.00000	4,800.00
203-01510	Backhoe	20.000	HOUR	160.00000	3,200.00	125.00000	2,500.00	225.00000	4,500.00
203-01594	Combination Loader	20.000	HOUR	150.00000	3,000.00	125.00000	2,500.00	225.00000	4,500.00
203-02330	Laborer	40.000	HOUR	60.00000	2,400.00	45.00000	1,800.00	100.00000	4,000.00
206-00000	Structure Excavation	73.000	CY	45.00000	3,285.00	20.00000	1,460.00	11.75000	857.75
206-00065	Structure Backfill (Flow-Fill)	57.000	CY	400.00000	22,800.00	200.00000	11,400.00	210.00000	11,970.00
206-01750	Shoring	1.000	LS	23,000.00000	23,000.00	2,500.00000	2,500.00	67,000.00000	67,000.00
207-00205	Topsoil	98.000	CY	20.00000	1,960.00	55.00000	5,390.00	99.00000	9,702.00
208-00002	Erosion Log Type 1 (12 Inch)	36.000	LF	8.00000	288.00	4.00000	144.00	6.25000	225.00

Page 2 of 5

07/23/2020

Printed On:

	(0 Engine				(1) 1721 Frontier Environmental Services, LLC		(2) 1282 AMERICAN CONSTRUCTI	WEST
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
208-00011	Erosion Bales (Weed Free)	24.000 EACH	25.00000	600.00	25.00000	600.00	24.00000	576.00
208-00020	Silt Fence	358.000 LF	3.00000	1,074.00	3.00000	1,074.00	2.60000	930.80
208-00041	Rock Check Dam	4.000 EACH	500.00000	2,000.00	500.00000	2,000.00	1,100.00000	4,400.00
208-00045	Concrete Washout Structure	3.000 EACH	2,500.00000	7,500.00	750.00000	2,250.00	1,100.00000	3,300.00
208-00070	Vehicle Tracking Pad	2.000 EACH	3,000.00000	6,000.00	1,500.00000	3,000.00	3,900.00000	7,800.00
208-00103	Removal and Disposal of Sediment (Labor)	80.000 HOUR	60.00000	4,800.00	80.00000	6,400.00	100.00000	8,000.00
208-00105	Removal and Disposal of Sediment (Equipment)	80.000 HOUR	150.00000	12,000.00	215.00000	17,200.00	225.00000	18,000.00
208-00107	Removal of Trash	20.000 HOUR	150.00000	3,000.00	45.00000	900.00	70.00000	1,400.00
208-00207	Erosion Control Management	30.000 DAY	300.00000	9,000.00	95.00000	2,850.00	68.50000	2,055.00
208-00400	Water Control	1.000 LS	35,000.00000	35,000.00	15,000.00000	15,000.00	13,000.00000	13,000.00
210-00011	Reset Mailbox Structure (Type 1)	1.000 EACH	500.00000	500.00	250.00000	250.00	860.00000	860.00
211-02277	Cement Grout (Voids)	1.000 CY	1,500.00000	1,500.00	1,000.00000	1,000.00	8,100.00000	8,100.00
212-00006	Seeding (Native)	0.190 ACRE	1,600.00000	304.00	3,500.00000	665.00	12,000.00000	2,280.00
212-00032	Soil Conditioning	0.190 ACRE	2,500.00000	475.00	3,750.00000	712.50	8,000.00000	1,520.00
216-00201	Soil Retention Blanket (Straw-Coconut) (Biodegradable Class 1)	463.000 SY	5.00000	2,315.00	4.00000	1,852.00	4.50000	2,083.50

Page 3 of 5

07/23/2020

Printed On:

		Contract ID.		(0) -EST- Engineer's Estimate		(1) 1721 Frontier Environmental Services, LLC		(2) 1282 AMERICAN CONSTRUCTI	WEST
Item Code	Description	Quar	itity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS						LCC:		
216-00301	Turf Reinforcement Mat (Class 1)	424.000	SY	8.00000	3,392.00	5.25000	2,226.00	7.75000	3,286.00
240-00010	Removal of Nests	20.000	HOUR	140.00000	2,800.00	135.00000	2,700.00	59.75000	1,195.00
240-00020	Netting	22.000	SY	10.00000	220.00	50.00000	1,100.00	27.25000	599.50
304-06007	Aggregate Base Course (Class 6)	21.000	CY	60.00000	1,260.00	185.00000	3,885.00	120.00000	2,520.00
403-34721	Hot Mix Asphalt (Grading SX) (75) (PG 58-28)	13.900	TON	100.00000	1,390.00	350.00000	4,865.00	790.00000	10,981.00
411-10255	Emulsified Asphalt (Slow-Setting)	9.000	GAL	6.00000	54.00	25.00000	225.00	18.00000	162.00
420-00112	Geotextile (Drainage) (Class 1)	16.000	SY	6.00000	96.00	6.50000	104.00	19.50000	312.00
506-00209	Riprap (9 Inch)	31.000	CY	140.00000	4,340.00	115.00000	3,565.00	220.00000	6,820.00
601-01010	Concrete Class BZ	103.000	CY	800.0000	82,400.00	255.00000	26,265.00	410.00000	42,230.00
603-00078	Culvert Lining (78 Inch)	120.000	LF	600.00000	72,000.00	320.00000	38,400.00	620.00000	74,400.00
607-11525	Fence (Plastic)	117.000	LF	5.00000	585.00	2.50000	292.50	3.45000	403.65
620-00020	Sanitary Facility	2.000	EACH	3,000.00000	6,000.00	650.00000	1,300.00	230.00000	460.00
624-23049	48 Inch Drainage Pipe (Class 3) (Complete In Place)	153.000	LF	320.00000	48,960.00	282.00000	43,146.00	350.00000	53,550.00
625-00000	Construction Surveying	1.000	LS	30,000.00000	30,000.00	2,500.00000	2,500.00	4,500.00000	4,500.00
626-00000	Mobilization	1.000	LS	74,482.00000	74,482.00	32,000.00000	32,000.00	108,000.00000	108,000.00

Page 4 of 5

07/23/2020

Printed On:

				(0) -EST Engineer's Es		(1) 1721 Frontier Environmental		(2) 1282 AMERICAN	
						Services, LLC		CONSTRUCTI	
Item Code	Description	Quantity	y	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS						LCC:		
626-01114	Public Information Management (Tier IV)	67.000 D	PAY	75.00000	5,025.00	75.00000	5,025.00	68.50000	4,589.50
627-00005	Epoxy Pavement Marking	2.000 G	SAL	120.00000	240.00	3,450.00000	6,900.00	1,800.00000	3,600.00
630-00000	Flagging	200.000 HO	UR	35.00000	7,000.00	30.00000	6,000.00	30.00000	6,000.00
630-00007	Traffic Control Inspection	15.000 D	PAY	300.00000	4,500.00	350.00000	5,250.00	360.00000	5,400.00
630-00012	Traffic Control Management	38.000 D	PAY	900.00000	34,200.00	900.00000	34,200.00	900.00000	34,200.00
630-80001	Flashing Beacon (Portable)	6.000 EAG	СН	800.0000	4,800.00	1,425.00000	8,550.00	1,400.00000	8,400.00
630-80341	Construction Traffic Sign (Panel Size A)	16.000 EAG	СН	50.00000	800.00	48.00000	768.00	47.75000	764.00
630-80342	Construction Traffic Sign (Panel Size B)	44.000 EAG	СН	80.00000	3,520.00	90.00000	3,960.00	89.75000	3,949.00
630-80350	Vertical Panel	60.000 EAG	СН	35.00000	2,100.00	48.00000	2,880.00	47.75000	2,865.00
630-80354	Vertical Panel (With Light) (Steady Burn)	20.000 EAG	СН	45.00000	900.00	60.00000	1,200.00	59.75000	1,195.00
630-80355	Portable Message Sign Panel	2.000 EAG	СН	6,000.00000	12,000.00	1,550.00000	3,100.00	3,000.00000	6,000.00
630-80358	Advance Warning Flashing or Sequencing Arrow Panel (C Type)	2.000 EAG	СН	2,000.00000	4,000.00	600.00000	1,200.00	600.00000	1,200.00
630-80360	Drum Channelizing Device	10.000 EAG	СН	35.00000	350.00	60.00000	600.00	59.75000	597.50
630-80370	Barrier (Temporary)	240.000	LF	50.00000	12,000.00	55.00000	13,200.00	63.75000	15,300.00
630-80371	Reset Concrete Barrier (Temporary)	240.000	LF	20.00000	4,800.00	5.00000	1,200.00	18.00000	4,320.00

Tabulation of Bids

Page 5 of 5

07/23/2020

Printed On:

			(0) -EST- Engineer's Estimate		(1) 1721 Frontier Environmental Services, LLC		Engineer's Estimate Frontier Environmental AMERICAN		WEST
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount	
SECTION:	0001 BID ITEMS					LCC:			
630-80380	Traffic Cone	100.000 EACH	10.00000	1,000.00	6.00000	600.00	12.00000	1,200.00	
630-80430	Rumble Strip (Portable)	6.000 EACH	2,000.00000	12,000.00	2,000.00000	12,000.00	3,000.00000	18,000.00	
630-85010	Impact Attenuator (Temporary)	2.000 EACH	5,500.00000	11,000.00	8,300.00000	16,600.00	8,400.00000	16,800.00	
630-85040	Impact Attenuator (Truck Mounted Attenuator) (Temporary)	2.000 EACH	8,000.00000	16,000.00	6,000.00000	12,000.00	6,000.00000	12,000.00	
630-86810	Traffic Signal (Temporary)	2.000 EACH	25,000.00000	50,000.00	7,100.00000	14,200.00	3,600.00000	7,200.00	
632-00000	Night Work Lighting	1.000 LS	25,000.00000	25,000.00	2,200.00000	2,200.00	5,300.00000	5,300.00	
Section To	tals:		\$72	5,000.00	\$42	24,274.00	\$69	96,485.70	
Contract (Grand Totals	\$72	25,000.00	\$42	24,274.00	\$6	96,485.70		

Low Bid Item Analysis

Page 1 of 6

07/23/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0005	201-00000 Clearing and Gru	1.000 abbing	9,600.00000	3,500.00000 L S	9,600.00	3,500.00	36.46%	-6,100.00
0010	201-00007 Removal of Debr	1.000 is	600.00000	250.00000 EACH	600.00	250.00	41.67%	-350.00
0015	202-00010 Removal of Tree	2.000	250.00000	250.00000 EACH	500.00	500.00	100.00%	0.00
0020	202-00150 Removal of Wall	1.000	8,000.00000	2,000.00000 EACH	8,000.00	2,000.00	25.00%	-6,000.00
0025	202-00220 Removal of Asph	42.000 nalt Mat	20.00000	36.00000 SY	840.00	1,512.00	180.00%	672.00
0030	202-04008 Clean Culvert	122.000	65.00000	45.00000 LF	7,930.00	5,490.00	69.23%	-2,440.00
0035	203-00060 Embankment Ma	209.000 terial (Complete In	35.00000 Place)	52.00000 CY	7,315.00	10,868.00	148.57%	3,553.00
0040	203-01500 Blading	20.000	250.00000	125.00000 HOUR	5,000.00	2,500.00	50.00%	-2,500.00
0045	203-01510 Backhoe	20.000	160.00000	125.00000 HOUR	3,200.00	2,500.00	78.13%	-700.00
0050	203-01594 Combination Loa	20.000 der	150.00000	125.00000 HOUR	3,000.00	2,500.00	83.33%	-500.00
0055	203-02330 Laborer	40.000	60.00000	45.00000 HOUR	2,400.00	1,800.00	75.00%	-600.00
0060	206-00000 Structure Excava	73.000 ation	45.00000	20.00000 CY	3,285.00	1,460.00	44.44%	-1,825.00

Low Bid Item Analysis

Page 2 of 6

07/23/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0065	206-00065 Structure Backfil	57.000 I (Flow-Fill)	400.00000	200.00000 CY	22,800.00	11,400.00	50.00%	-11,400.00
0070	206-01750 Shoring	1.000	23,000.00000	2,500.00000 L S	23,000.00	2,500.00	10.87%	-20,500.00
0075	207-00205 Topsoil	98.000	20.00000	55.00000 CY	1,960.00	5,390.00	275.00%	3,430.00
0800	208-00002 Erosion Log Typ	36.000 e 1 (12 Inch)	8.00000	4.00000 LF	288.00	144.00	50.00%	-144.00
0085	208-00011 Erosion Bales (V	24.000 Veed Free)	25.00000	25.00000 EACH	600.00	600.00	100.00%	0.00
0090	208-00020 Silt Fence	358.000	3.00000	3.00000 LF	1,074.00	1,074.00	100.00%	0.00
0095	208-00041 Rock Check Dar	4.000 n	500.00000	500.00000 EACH	2,000.00	2,000.00	100.00%	0.00
0100	208-00045 Concrete Washo	3.000 out Structure	2,500.00000	750.00000 EACH	7,500.00	2,250.00	30.00%	-5,250.00
0105	208-00070 Vehicle Tracking	2.000 Pad	3,000.00000	1,500.00000 EACH	6,000.00	3,000.00	50.00%	-3,000.00
0110	208-00103 Removal and Dis	80.000 sposal of Sediment	60.00000 (Labor)	80.00000 HOUR	4,800.00	6,400.00	133.33%	1,600.00
0115	208-00105 Removal and Dis	80.000 sposal of Sediment	150.00000 (Equipment)	215.00000 HOUR	12,000.00	17,200.00	143.33%	5,200.00
0120	208-00107 Removal of Tras	20.000 h	150.00000	45.00000 HOUR	3,000.00	900.00	30.00%	-2,100.00

Low Bid Item Analysis

Page 3 of 6

07/23/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0125	208-00207 Erosion Control I	30.000 Management	300.00000	95.00000 DAY	9,000.00	2,850.00	31.67%	-6,150.00
0130	208-00400 Water Control	1.000	35,000.00000	15,000.00000 L S	35,000.00	15,000.00	42.86%	-20,000.00
0135	210-00011 Reset Mailbox S	1.000 tructure (Type 1)	500.00000	250.00000 EACH	500.00	250.00	50.00%	-250.00
0140	211-02277 Cement Grout (V	1.000 /oids)	1,500.00000	1,000.00000 CY	1,500.00	1,000.00	66.67%	-500.00
0145	212-00006 Seeding (Native)	0.190	1,600.00000	3,500.00000 ACRE	304.00	665.00	218.75%	361.00
0150	212-00032 Soil Conditioning	0.190	2,500.00000	3,750.00000 ACRE	475.00	712.50	150.00%	237.50
0155	216-00201 Soil Retention Bl (Biodegradable 0	463.000 anket (Straw-Cocor Class 1)	5.00000 nut)	4.00000 SY	2,315.00	1,852.00	80.00%	-463.00
0160	216-00301 Turf Reinforceme	424.000 ent Mat (Class 1)	8.00000	5.25000 SY	3,392.00	2,226.00	65.63%	-1,166.00
0165	240-00010 Removal of Nest	20.000 s	140.00000	135.00000 HOUR	2,800.00	2,700.00	96.43%	-100.00
0170	240-00020 Netting	22.000	10.00000	50.00000 SY	220.00	1,100.00	500.00%	880.00
0175	304-06007 Aggregate Base	21.000 Course (Class 6)	60.00000	185.00000 CY	1,260.00	3,885.00	308.33%	2,625.00
0180	403-34721 Hot Mix Asphalt	13.900 (Grading SX) (75) (100.00000 PG 58-28)	350.00000 TON	1,390.00	4,865.00	350.00%	3,475.00

Low Bid Item Analysis

Page 4 of 6

07/23/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0185	411-10255 Emulsified Aspha	9.000 It (Slow-Setting)	6.00000	25.00000 GAL	54.00	225.00	416.67%	171.00
0190	420-00112 Geotextile (Drain	16.000 age) (Class 1)	6.00000	6.50000 SY	96.00	104.00	108.33%	8.00
0195	506-00209 Riprap (9 Inch)	31.000	140.00000	115.00000 CY	4,340.00	3,565.00	82.14%	-775.00
0200	601-01010 Concrete Class E	103.000 SZ	800.00000	255.00000 CY	82,400.00	26,265.00	31.88%	-56,135.00
0205	603-00078 Culvert Lining (78	120.000 3 Inch)	600.00000	320.00000 LF	72,000.00	38,400.00	53.33%	-33,600.00
0210	607-11525 Fence (Plastic)	117.000	5.00000	2.50000 LF	585.00	292.50	50.00%	-292.50
0215	620-00020 Sanitary Facility	2.000	3,000.00000	650.00000 EACH	6,000.00	1,300.00	21.67%	-4,700.00
0220	624-23049 48 Inch Drainage Place)	153.000 Pipe (Class 3) (Co	320.00000 omplete In	282.00000 LF	48,960.00	43,146.00	88.13%	-5,814.00
0225	625-00000 Construction Sur	1.000 veying	30,000.00000	2,500.00000 L S	30,000.00	2,500.00	8.33%	-27,500.00
0230	626-00000 Mobilization	1.000	74,482.00000	32,000.00000 L S	74,482.00	32,000.00	42.96%	-42,482.00
0235	626-01114 Public Information	67.000 n Management (Tie	75.00000 er IV)	75.00000 DAY	5,025.00	5,025.00	100.00%	0.00
0240	627-00005 Epoxy Pavement	2.000 Marking	120.00000	3,450.00000 GAL	240.00	6,900.00	2875.00%	6,660.00

Low Bid Item Analysis

Page 5 of 6

07/23/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0245	630-00000 Flagging	200.000	35.00000	30.00000 HOUR	7,000.00	6,000.00	85.71%	-1,000.00
0250	630-00007 Traffic Control In	15.000 spection	300.00000	350.00000 DAY	4,500.00	5,250.00	116.67%	750.00
0255	630-00012 Traffic Control M	38.000 anagement	900.00000	900.00000 DAY	34,200.00	34,200.00	100.00%	0.00
0260	630-80001 Flashing Beacor	6.000 (Portable)	800.00000	1,425.00000 EACH	4,800.00	8,550.00	178.13%	3,750.00
0265	630-80341 Construction Tra	16.000 iffic Sign (Panel Size	50.00000 e A)	48.00000 EACH	800.00	768.00	96.00%	-32.00
0270	630-80342 Construction Tra	44.000 iffic Sign (Panel Size	80.00000 e B)	90.00000 EACH	3,520.00	3,960.00	112.50%	440.00
0275	630-80350 Vertical Panel	60.000	35.00000	48.00000 EACH	2,100.00	2,880.00	137.14%	780.00
0280	630-80354 Vertical Panel (V	20.000 Vith Light) (Steady E	45.00000 Burn)	60.00000 EACH	900.00	1,200.00	133.33%	300.00
0285	630-80355 Portable Messag	2.000 ge Sign Panel	6,000.00000	1,550.00000 EACH	12,000.00	3,100.00	25.83%	-8,900.00
0290	630-80358 Advance Warnin Panel (C Type)	2.000 g Flashing or Seque	2,000.00000 encing Arrow	600.00000 EACH	4,000.00	1,200.00	30.00%	-2,800.00
0295	630-80360 Drum Channelizi	10.000 ing Device	35.00000	60.00000 EACH	350.00	600.00	171.43%	250.00
0300	630-80370 Barrier (Tempora	240.000 ary)	50.00000	55.00000 LF	12,000.00	13,200.00	110.00%	1,200.00

Low Bid Item Analysis

Printed On:

Page 6 of 6

07/23/2020

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0305	630-80371 Reset Concrete	240.000 Barrier (Temporary)	20.00000	5.00000 LF	4,800.00	1,200.00	25.00%	-3,600.00
0310	630-80380 Traffic Cone	100.000	10.00000	6.00000 EACH	1,000.00	600.00	60.00%	-400.00
0315	630-80430 6.000 Rumble Strip (Portable)		2,000.00000	2,000.00000 EACH	12,000.00	12,000.00	100.00%	0.00
0320	630-85010 Impact Attenuate	2.000 or (Temporary)	5,500.00000	8,300.00000 EACH	11,000.00	16,600.00	150.91%	5,600.00
0325	630-85040 2.000 8,000.00000 Impact Attenuator (Truck Mounted Attenuator) (Temporary)			6,000.00000 EACH	16,000.00	12,000.00	75.00%	-4,000.00
0330	630-86810 Traffic Signal (To	2.000 emporary)	25,000.00000	7,100.00000 EACH	50,000.00	14,200.00	28.40%	-35,800.00
0335	632-00000 Night Work Ligh	1.000 ting	25,000.00000	2,200.00000 L S	25,000.00	2,200.00	8.80%	-22,800.00
Section 0001 Subtotal					\$725,000.00	\$424,274.00	58.52%	-\$300,726.00
Contract Total for Calculated Low Bidders Bid Items					\$725,000.00	\$424,274.00	58.52%	-\$300,726.00