Colorado Department Of Transportation Low Bid Summary

Printed On:

Page 1 of 1

04/09/2020

Letting Date: April 09, 2020

Call Order	Contract ID	Project(s)	# of Bids	Low Bidder	Estimated Cost	Corrected Bid	Percent of Estimate	Overrun (+) Underrun (-)
007	C21257	NHPP1601-077	3	INTERMOUNTAIN SLURRY SEAL, INC.	\$1,567,257.80	\$1,303,347.00	83.16%	-\$263,910.80
Letti	ng Totals		3		\$1,567,257.80	\$1,303,347.00	83.16%	-\$263,910.80

Vendor Ranking

Printed On: 04/09/2020 Page 1 of 1

Contract ID: C21257

Contract Description:

This project is located on US 160 from mile point (MP) 29.750 to MP 34.891 in Montezuma County for a total project length of 5.141 miles.

The work begins 2 miles north of Towaoc and ends 1000' south of the southern edge of the concrete pavement at the intersection with Montezuma CR G.

Consisting of a double lift chipseal with a micro-surfacing top lift. The first lift of chips will be Type 2 and the second lift will be Type 1. Chipseal will utilize CRS-2P Emulsion. Microsurfacing will be placed on top of both lifts of chips.

Temporary striping shall be required after placement of each lift of chips, and after the microsurfacing application. Rumble strips shall be placed at least 10 days after the micro-surfacing has been placed.

Final striping shall be applied at least 14 calendar days after placement of the micro-surfacing application.

Both temporary and final striping will be in form of High-Build Pavement Marking Paint.

Rank	Vendor ID	Vendor Name	Total Bid	Percent Of Low Bid	Percent Of Estimate
1	110E	INTERMOUNTAIN SLURRY SEAL, INC.	\$1,303,347.00	100.00%	83.16%
2	672A	OLDCASTLE SW GROUP, INC.	\$1,444,169.90	110.80%	92.15%
0	-EST-	Engineer's Estimate	\$1,567,257.80	120.25%	100.00%
3	621A	GMCO LIMITED LIABILITY COMPANY OF COLORADO	\$1,620,301.87	124.32%	103.38%

Page 1 of 4

04/09/2020

Printed On:

			(0) -EST- Engineer's Estimate		(1) 110I Intermoun Slurry Sea	NIATN	(2) 672. OLDCASTL GROUP, I	E SW
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
208-00002	Erosion Log Type 1 (12 Inch)	200.000 LF	5.00000	1,000.00	5.00000	1,000.00	4.35000	870.00
208-00103	Removal and Disposal of Sediment (Labor)	8.000 HOUF	50.00000	400.00	50.00000	400.00	54.00000	432.00
208-00106	Sweeping (Sediment Removal)	8.000 HOUF	350.00000	2,800.00	150.00000	1,200.00	110.00000	880.00
409-01015	Cover Coat Material (Type I)	130,383.000 SY	1.10000	143,421.30	0.75000	97,787.25	1.00000	130,383.00
409-02015	Cover Coat Material (Type II)	130,383.000 SY	1.25000	162,978.75	0.75000	97,787.25	1.05000	136,902.15
409-09000	Micro-Surfacing Seal Coat	2,054.000 TON	350.00000	718,900.00	210.00000	431,340.00	240.00000	492,960.00
411-10216	Emulsified Asphalt (CRS-2P)	86,053.000 GAI	2.50000	215,132.50	3.75000	322,698.75	3.00000	258,159.00
614-73005	Piezo (Electric) (Class II)	2.000 EACH	3,000.00000	6,000.00	12,000.00000	24,000.00	3,000.00000	6,000.00
614-80391	Rumble Strip (Grinding)(Asphalt)	37,155.000 LF	0.35000	13,004.25	0.25000	9,288.75	0.25000	9,288.75
626-00000	Mobilization	1.000 L S	150,000.00000	150,000.00	190,000.00000	190,000.00	236,500.00000	236,500.00
626-01114	Public Information Management (Tier IV)	83.000 DAY	72.00000	5,976.00	40.00000	3,320.00	45.00000	3,735.00
627-00013	Pavement Marking Paint (High Build)	512.000 GAI	30.00000	15,360.00	36.00000	18,432.00	35.00000	17,920.00
627-00013	Pavement Marking Paint (High Build) (Temporary)	855.000 GAI	30.00000	25,650.00	30.00000	25,650.00	60.00000	51,300.00
630-00000	Flagging	1,600.000 HOUF	25.00000	40,000.00	15.00000	24,000.00	23.00000	36,800.00
630-00001	Pilot Car Operation	200.000 HOUF	45.00000	9,000.00	50.00000	10,000.00	50.00000	10,000.00

Page 2 of 4

04/09/2020

Printed On:

			(0) -EST- Engineer's Estimate				(2) 672 OLDCASTL GROUP,	E SW
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
630-00007	Traffic Control Inspection	25.000 DAY	110.00000	2,750.00	145.00000	3,625.00	350.00000	8,750.00
630-00012	Traffic Control Management	25.000 DAY	800.0000	20,000.00	600.00000	15,000.00	650.00000	16,250.00
630-80341	Construction Traffic Sign (Panel Size A)	10.000 EACH	40.00000	400.00	22.00000	220.00	23.00000	230.00
630-80342	Construction Traffic Sign (Panel Size B)	62.000 EACH	40.00000	2,480.00	44.00000	2,728.00	35.00000	2,170.00
630-80350	Vertical Panel	30.000 EACH	27.00000	810.00	20.00000	600.00	23.00000	690.00
630-80355	Portable Message Sign Panel	2.000 EACH	2,000.00000	4,000.00	3,000.00000	6,000.00	3,500.00000	7,000.00
630-80360	Drum Channelizing Device	35.000 EACH	27.00000	945.00	22.00000	770.00	20.00000	700.00
630-80511	Mobile Pavement Marking Zone	1.000 LS	10,000.00000	10,000.00	12,500.00000	12,500.00	10,000.00000	10,000.00
630-85041	Mobile Attenuator	25.000 DAY	650.00000	16,250.00	200.00000	5,000.00	250.00000	6,250.00
Section To	tals:		\$1,56	7,257.80	\$1,30	3,347.00	\$1,44	4,169.90
Contract (Grand Totals	\$1,567,257.80		\$1,303,347.00		\$1,444,169.90		

Page 3 of 4

04/09/2020

Printed On:

			(3) 621A GMCO LLC OF COLORADO		
Item Code	Description	Quantity	Unit Price Amount	Unit Price Amount	Unit Price Amount
SECTION:	0001 BID ITEMS			LCC:	
208-00002	Erosion Log Type 1 (12 Inch)	200.000 LF	15.00000 3,000.00		
208-00103	Removal and Disposal of Sediment (Labor)	8.000 HOUR	60.00000 480.00		
208-00106	Sweeping (Sediment Removal)	8.000 HOUR	250.00000 2,000.00		
409-01015	Cover Coat Material (Type I)	130,383.000 SY	1.03000 134,294.49)	
409-02015	Cover Coat Material (Type II)	130,383.000 SY	1.10000 143,421.30		
409-09000	Micro-Surfacing Seal Coat	2,054.000 TON	275.00000 564,850.00		
411-10216	Emulsified Asphalt (CRS-2P)	86,053.000 GAL	3.11000 267,624.83	3	
614-73005	Piezo (Electric) (Class II)	2.000 EACH	10,000.00000 20,000.00		
614-80391	Rumble Strip (Grinding)(Asphalt)	37,155.000 LF	0.15000 5,573.25	5	
626-00000	Mobilization	1.000 LS	284,500.00000 284,500.00		
626-01114	Public Information Management (Tier IV)	83.000 DAY	78.00000 6,474.00		
627-00013	Pavement Marking Paint (High Build)	512.000 GAL	47.00000 24,064.00		
627-00013	Pavement Marking Paint (High Build) (Temporary)	855.000 GAL	63.00000 53,865.00		
630-00000	Flagging	1,600.000 HOUR	26.00000 41,600.00		
630-00001	Pilot Car Operation	200.000 HOUR	50.00000 10,000.00		

Page 4 of 4

04/09/2020

Printed On:

			(3) 621A GMCO LLC OF COLORADO					
Item Code	Description	Quantity	Unit Price	Amount	Unit Price	Amount	Unit Price	Amount
SECTION:	0001 BID ITEMS					LCC:		
630-00007	Traffic Control Inspection	25.000 DAY	85.00000	2,125.00				
630-00012	Traffic Control Management	25.000 DAY	800.00000	20,000.00				
630-80341	Construction Traffic Sign (Panel Size A)	10.000 EACH	40.00000	400.00				
630-80342	Construction Traffic Sign (Panel Size B)	62.000 EACH	40.00000	2,480.00				
630-80350	Vertical Panel	30.000 EACH	25.00000	750.00				
630-80355	Portable Message Sign Panel	2.000 EACH	4,500.00000	9,000.00				
630-80360	Drum Channelizing Device	35.000 EACH	30.00000	1,050.00				
630-80511	Mobile Pavement Marking Zone	1.000 LS	6,500.00000	6,500.00				
630-85041	Mobile Attenuator	25.000 DAY	650.00000	16,250.00				
Section To	tals:		\$1,62	0,301.87				
Contract (Grand Totals		\$1,62	20,301.87				

Low Bid Item Analysis

Page 1 of 3

04/09/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0005	208-00002 Erosion Log Typ	200.000 e 1 (12 Inch)	5.00000	5.00000 LF	1,000.00	1,000.00	100.00%	0.00
0010	208-00103 Removal and Dis	8.000 sposal of Sediment	50.00000 (Labor)	50.00000 HOUR	400.00	400.00	100.00%	0.00
0015	208-00106 Sweeping (Sedir	8.000 ment Removal)	350.00000	150.00000 HOUR	2,800.00	1,200.00	42.86%	-1,600.00
0020	409-01015 Cover Coat Mate	130,383.00 erial (Type I)	1.10000	0.75000 SY	143,421.30	97,787.25	68.18%	-45,634.05
0025	409-02015 Cover Coat Mate	130,383.00 erial (Type II)	1.25000	0.75000 SY	162,978.75	97,787.25	60.00%	-65,191.50
0030	409-09000 Micro-Surfacing	2,054.000 Seal Coat	350.00000	210.00000 TON	718,900.00	431,340.00	60.00%	-287,560.00
0035	411-10216 Emulsified Aspha	86,053.000 alt (CRS-2P)	2.50000	3.75000 GAL	215,132.50	322,698.75	150.00%	107,566.25
0040	614-73005 Piezo (Electric) (2.000 Class II)	3,000.00000	12,000.00000 EACH	6,000.00	24,000.00	400.00%	18,000.00
0045	614-80391 Rumble Strip (G	37,155.000 rinding)(Asphalt)	0.35000	0.25000 LF	13,004.25	9,288.75	71.43%	-3,715.50
0050	626-00000 Mobilization	1.000	150,000.00000	190,000.00000 L S	150,000.00	190,000.00	126.67%	40,000.00
0055	626-01114 Public Information	83.000 on Management (Tie	72.00000 er IV)	40.00000 DAY	5,976.00	3,320.00	55.56%	-2,656.00
0060	627-00013 Pavement Marki	512.000 ng Paint (High Build	30.00000 d)	36.00000 GAL	15,360.00	18,432.00	120.00%	3,072.00

Low Bid Item Analysis

Page 2 of 3

04/09/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
SECTION:	0001	BID ITEMS						
0065	627-00013 Pavement Marki (Temporary)	855.000 ng Paint (High Build	30.00000 d)	30.00000 GAL	25,650.00	25,650.00	100.00%	0.00
0070	630-00000 Flagging	1,600.000	25.00000	15.00000 HOUR	40,000.00	24,000.00	60.00%	-16,000.00
0075	630-00001 Pilot Car Operat	200.000 ion	45.00000	50.00000 HOUR	9,000.00	10,000.00	111.11%	1,000.00
0800	630-00007 Traffic Control Ir	25.000 aspection	110.00000	145.00000 DAY	2,750.00	3,625.00	131.82%	875.00
0085	630-00012 Traffic Control M	25.000 lanagement	800.00000	600.00000 DAY	20,000.00	15,000.00	75.00%	-5,000.00
0090	630-80341 Construction Tra	10.000 affic Sign (Panel Siz	40.00000 e A)	22.00000 EACH	400.00	220.00	55.00%	-180.00
0095	630-80342 Construction Tra	62.000 affic Sign (Panel Siz	40.00000 e B)	44.00000 EACH	2,480.00	2,728.00	110.00%	248.00
0100	630-80350 Vertical Panel	30.000	27.00000	20.00000 EACH	810.00	600.00	74.07%	-210.00
0105	630-80355 Portable Messa	2.000 ge Sign Panel	2,000.00000	3,000.00000 EACH	4,000.00	6,000.00	150.00%	2,000.00
0110	630-80360 Drum Channeliz	35.000 ing Device	27.00000	22.00000 EACH	945.00	770.00	81.48%	-175.00
0115	630-80511 Mobile Pavemer	1.000 nt Marking Zone	10,000.00000	12,500.00000 L S	10,000.00	12,500.00	125.00%	2,500.00
0120	630-85041 Mobile Attenuate	25.000 or	650.00000	200.00000 DAY	16,250.00	5,000.00	30.77%	-11,250.00

Low Bid Item Analysis

Page 3 of 3

04/09/2020

Printed On:

Line	Item/ Description	Quantity	Estimated Price	Bid Price/ Units	Estimated Amount	Bid Amount	Bid Est %	Overrun (+) Underrun (-)
Section 00	001 Subtotal				\$1,567,257.80	\$1,303,347.00	83.16%	-\$263,910.80
Contrac	t Total for Calc	ulated Low Bidd	ers Bid Items		\$1,567,257.80	\$1,303,347.00	83.16%	-\$263,910.80